



Inspection and Maintenance Manual

for

FRP Composite Structures

March 30, 2021

TABLE OF CONTENTS

STATEMENT OF PURPOSE	4
TERMS, DEFINITIONS, AND ABBREVIATIONS	5
INTRODUCTION TO COMPOSITES	7
INSPECTION	14
1. WHAT TO INSPECT	14
2. STRUCTURAL COMPONENTS	14
a) <i>Substructure</i>	14
b) <i>Substructure to Superstructure Connections</i>	16
c) <i>Headwalls</i>	16
d) <i>Superstructure</i>	20
CLASSIFYING OBSERVATIONS	23
1. SURFACE DISCOLORATION / FADING	23
2. FRP FIBER EXPOSURE AND ABRASION	24
3. DELAMINATION.....	25
4. SUBSURFACE SCRATCHES	26
5. LAMINATE PENETRATION AND GOUGES	27
6. CRACKING	29
7. BULGING OR BLISTERING	29
INSPECTION METHODS	30
1. VISUAL INSPECTION	30
2. NON-DESTRUCTIVE EVALUATION	30
a) <i>Tap Test</i>	30
b) <i>Ground Penetrating Radar</i>	30
c) <i>Ultrasonic</i>	31
d) <i>Infrared Thermography</i>	31
MAINTENANCE	32
1. PREVENTATIVE MAINTENANCE	32
2. MINOR REPAIRS.....	33
3. MAJOR REPAIRS	34
USEFUL RESOURCES	38
TIDE MILL NO. 2 BRIDGE INSPECTION REPORT - EDMUNDS TOWNSHIP, ME	39
SKYPLEX BOULEVARD BRIDGE INSPECTION REPORT - FT. MYERS, FL	60
ROYAL RIVER BRIDGE INSPECTION REPORT - AUBURN, ME	123

TABLE OF FIGURES

Figure 1: GArch Infusion Flow Front during Infusion	7
Figure 2: Examples of Consumer Composites	8
Figure 3: Examples of Industrial Composites	9
Figure 4: Examples of Advanced Composites	10
Figure 5: GBeam System Hampden, ME	11
Figure 6: GArch System Duvall, WA.....	11
Figure 7: Example Composite Reinforcement Orientations.....	12
Figure 8 Precast Concrete Foundation for GArch System	15
Figure 9 Precast Driven Pile Deep Foundation System for GArch	15
Figure 10 Cast-in-Place Concrete Foundation for GArch System.....	16
Figure 11: Precast Through-Tied Headwall	17
Figure 12: Precast MSE Panel Headwall.....	17
Figure 13: Precast Modular Gravity Headwall.....	18
Figure 14: Precast Cantilevered Headwall	18
Figure 15: Precast MSE Block Headwall.....	19
Figure 16: Cast-in-Place Headwall.....	19
Figure 17: Example GBeam Top Flange with Sinusoidal Roughening	22
Figure 18: Corresponding Concrete Roughened Surface	23
Figure 19: Example of Fading and Discoloration after UV Exposure	24
Figure 20: Examples of Fiber Exposure or Abrasion	25
Figure 21: Example of Delamination around a Drilled Hole.....	26
Figure 22: Examples of Subsurface Scratching.....	27
Figure 23: Example of Laminate Penetration	28
Figure 24: Example of Laminate Gouging.....	29
Figure 25: Example of Blistering or Bulging.....	30
Figure 26 Ultrasonic Testing Equipment with Handheld Transducer and Output Display	31
Figure 27 Infrared Thermography Schematic	32
Figure 28 Heat Map Display Indicating Temperature Differential at the Sample Surface.....	32
Figure 29: Wet Layup Process	34
Figure 30: Example of Repair Mapping	34
Figure 31: Major Repair Preparation and Material Removal.....	35
Figure 32: Repair Layup Following Material and Layer Specifications	36
Figure 33: Repair Infusion	36
Figure 34: Completed Major Repair	37

STATEMENT OF PURPOSE

The purpose of this manual is to assist owners, end users, engineers, and others tasked with conducting Field Inspection (FI) and Preventive Maintenance (PM) of fiber-reinforced polymer (FRP) bridge structural elements engineered and manufactured by AIT Bridges, a division of Advanced Infrastructure Technologies, Inc. This manual, in conjunction with referenced FRP and bridge industry standards, is intended to satisfy the needs of the Bridge Maintenance Engineer or Inspection Engineer for the purposes of long-term evaluation and condition tracking of their FRP bridge assets.

The intended use of this document is to augment existing agency or owner inspection and maintenance procedures of bridges. The frequency for routine inspection and reporting requirements of GArch and GBeam Bridge Systems and components should be consistent with existing agency requirements for bridges.

TERMS, DEFINITIONS, AND ABBREVIATIONS

AASHTO - American Association of State and Highway Transportation Officials

ACMA - American Composites Manufacturers Association

Braid - A structural material used as reinforcement in composite arches.

B-FRP - Basalt FRP

CCT - Certified Composites Technician

CIP - Cast-in-Place

Core - Foam, balsa, or honeycomb core material used for separating structural laminates.

Crosslinking - The chemical reaction and process that forms covalent bonds between polymer chains.

C-FRP - Carbon FRP

FHWA - Federal Highway Administration

FRP - Fiber Reinforced Polymer - A thermoset composite material consisting of a polymer matrix with fiber reinforcing.

GPR - Ground Penetrating Radar - A methodology of NDE that utilizes Ground Penetrating Radar.

G-FRP - Glass FRP

Initiator - An additive to the resin matrix that begins the crosslinking reaction (also referred to as catalysts)

IRT - Infrared Thermography - A methodology of NDE that utilizes infrared thermography.

Laminate - An FRP component composed of layers of reinforcements arranged in a prescribed architecture as determined by engineered mechanical properties to achieve a desired structural capacity.

Matrix - The hardened form of the cross-linked resin and initiator mixture.

MEKP - Methyl Ethyl Keytone Peroxide - An initiator for the resin matrix.

MSE - Mechanically Stabilized Earth

NBIS - National Bridge Inventory Standards

NDE - Non-Destructive Evaluation - A methodology by which material characteristics can be determined using equipment or processes that do not require destruction of the material.

PET - Polyethylene Terephthalate - A type of closed cell foam used as a core material.

Pigment - A liquid additive, approximately 3% by weight, used to color the resin used for part infusion.

Pot Life - The length of time an initiated resin system remains in liquid form at a constant temperature.

Resin - The matrix material that binds all the reinforcements together to create the laminate.

SCC - Self-Consolidating Concrete

Specific Strength - A materials strength divided by its density.

Thixotropic Additive - A material added to the resin matrix to increase its viscosity and prevent it from thinning over time. This is particularly important in wet layup fabrication when resin is applied to a vertical surface.

UT - Ultrasonic Testing - A methodology of NDE that utilizes ultrasonics.

UV - Ultraviolet Light - The spectrum of light that may cause long term damage to FRP components.

Veil - A fiber surface layer integral with the laminate structure used for protection against UV exposure, abrasion, and/or for aesthetic appearance.

INTRODUCTION TO COMPOSITES

Composites, in their most basic form, are created by joining two or more different materials to form a new material with unique properties. The resulting material typically exhibits some of the desired properties from each of the individual materials. Reinforced concrete is an example of this general definition of a composite material because it combines the ductility of reinforcing steel with the high compressive resistance of concrete. A more acute definition of composites, as it relates to infrastructure or structural components, is fiber reinforced polymer (FRP) matrix materials engineered for the specific load applied. These composite materials are well known for being equally as strong as steel while remaining much lighter. In the world of FRP composites, there are two types of materials that come together to form a finished product: the reinforcement and the matrix. The reinforcement provides the load carrying capability, while the matrix provides the means to distribute the loads to the reinforcements. The fibers provide the strength and stiffness, while the matrix acts as a binding material to allow these fibers to work in unison. The matrix material, reinforcements, and manufacturing method can all contribute to the surface quality of the finished product. Reinforcements can vary widely but typically fall into one of four categories: glass, aramid, basalt, and carbon fiber. The most common reinforcements used in infrastructure applications are glass and carbon fiber, but basalt fiber is likely to increase over time. Aramid fibers tend to be avoided due to their high degradation response to UV light. Common matrix materials are polymer type resin systems such as polyesters, polyurethanes, epoxies, or a hybrid system like epoxy-vinyl-esters.

Composites are broadly classified as Consumer, Industrial, and Advanced and have grown to encompass markets including Petroleum and Chemical Industries, Aerospace, Military, Performance Automotive, and recently Infrastructure.




Figure 1: GArch Infusion Flow Front during Infusion

Consumer composites were first introduced into the industry in the 1950's. Some of these products, such as boats, swimming pools, bath ware, sporting goods equipment, and automotive equipment, have played a large role in the consumer acceptance of composites. The durable, lightweight, and repeatable nature of these parts led many to look at other industries that could benefit from these characteristics.



Figure 2: Examples of Consumer Composites

Industrial Composites include applications that require chemical and corrosion resistance and performance in adverse environments. These include chemical process piping, underground fuel storage tanks, pressure vessels, and hundreds of other products where durability and specific strength

are primary characteristics. Typically, these products are exposed to highly acid or highly basic materials as well as high temperatures and pressure. These applications also need materials that exhibit excellent corrosion resistance, high strength-to-weight ratio, high stiffness-to-weight ratio, as well as providing an extended service life.



Figure 3: Examples of Industrial Composites

Advanced Composites are manufactured using the highest performance fiber reinforcement materials and resin systems, where the specific strength has been optimized all the while reducing weight and increasing aesthetic characteristics. Low maintenance is another key component for many of these highly technical and demanding products.





Figure 4: Examples of Advanced Composites

Composites for Infrastructure include GFRP, BFRP, and CFRP reinforcement bars, externally bonded reinforcement systems such as column wraps or CFRP strips, as well as AIT Bridges GArch and GBeam

Structural Composite Bridge Systems. The focus of this manual will be to provide guidance on the products and systems that AIT Bridges and AIT Manufacturing design and supply. The products discussed later in detail include GArch, GBeam, GBar, GDeck, GBolt, and GWall.

These applications demand low maintenance, high durability, high specific strength, and stiffness as well as corrosion resistance. Lightweight, sustainability, and resilience are bonus characteristics that these materials provide to the infrastructure market. Below are some examples of the applications mentioned.



Figure 5: GBeam System Hampden, ME



Figure 6: GArch System Duvall, WA

What differentiates composites from other structural materials? Metals are isotropic materials having identical properties in all directions where composites are anisotropic materials, meaning properties are directionally dependent. Composites are specifically engineered to provide strength and stiffness

properties in the directions needed. This is a key component which allows a designer to optimize a structural member to perform in a way that utilizes capacity where demand requires it and reduces it where it is not needed. FRP composites consist of reinforcements in different orientations to optimize the response of the structure. The most commonly used fabric is unidirectional, meaning fibers in one direction, and the next most commonly used fabric is biaxial, meaning fibers in two different directions like $0^\circ/90^\circ$ or $\pm 45^\circ$. If a component is in primarily tension or compression it will most likely be predominantly unidirectional fabric. If a component is primarily in shear, it would usually be reinforced with $\pm 45^\circ$ biaxial fabric. If a component is subjected to a mixture of stresses, the laminate typically has a mixture of unidirectional and biaxial reinforcements.




Figure 7: Example Composite Reinforcement Orientations

Fiber reinforcements are joined together using resin systems. Resin, also known as the matrix, is the binder that ties all the fibers together through the laminate stack. This matrix provides many characteristics, some of which may vary by formulation. These characteristics are strength and toughness, chemical, heat, UV, and abrasion resistance. Different resin systems provide varying results when it comes to these properties.

Another factor in determining a resin system is the process in which it is being applied to the laminate (e.g. wet layup, vacuum infusion, resin transfer, prepreg, etc.). These processes will require certain resin

properties that will allow it to be applied correctly. For example, a wet layup will require a resin system with thixotropic properties, allowing it to be worked into and saturating the fibers and not run back out during the curing process. For vacuum infusion, the resin needs to have a low enough viscosity and long enough pot life to allow the fibers to absorb it fully before setting up and not leaving any fibers dry or with voids in the laminate.

The resins used in these applications are classified as thermoset resins. Thermoset resins are resin systems that utilize an initiator, sometimes called a catalyst, to initiate a chemical reaction called crosslinking. This process is irreversible unlike thermoplastic resins where heat is applied, and the material is molded or formed into shape and cooled. When reheated thermoplastics can be remolded and reused, but do not offer the durability and heat resistance that thermoset resins offer.

INSPECTION

1. What to Inspect

The first and easiest inspection method is a thorough and systematic visual inspection of the entirety of each component. This will identify areas for further investigation. General photographs of the structure should be taken to document the condition as well as photographs of any observed concern.

If areas of concern are identified a physical examination can be undertaken. This can include feeling the suspected area by hand or with a probe and/or tapping to determine potential damaged area from distinct variations in sound.

In cases where structural damage is suspected, but unable to be detected or definitively determined by visual or physical methods, NDE methods should be employed. See list of NDE methodologies below in the section titled Inspection Methods.

2. Structural Components

a) Substructure

i. Types of Substructure

Cast in Place Reinforced Concrete Foundation

Precast Concrete Segmental Foundations

Deep Foundations (H-pile, Precast pile, micropile supported)

The substructure condition should be inspected, rated, and coded in accordance with standard practice given NBIS; FHWA Recording and Coding Guide for the Structure Inventory and Appraisal of the Nation's Bridges.



Figure 8 Precast Concrete Foundation for GArch System



Figure 9 Precast Driven Pile Deep Foundation System for GArch



Figure 10 Cast-in-Place Concrete Foundation for GArch System

b) Substructure to Superstructure Connections

The GArch system is embedded a minimum of 12 inches along the spine of the arch. The GDeck panel is typically embedded at least one inch along the spine of the arch into the substructure. This creates a fixed-fixed bearing condition where bending moment is translated into the foundation system. Special attention should be given to the area surrounding the arch and decking during inspection.

The GBeam system is usually placed on laminated elastomeric bearing pads or plain elastomeric bearing pads. Typically, there is a reinforced concrete end diaphragm that runs transverse to the bridge's longitudinal axis that encases the ends of the girder.

c) Headwalls

i. Types of Headwalls

Composite Panel or Sheet Pile Though Tied or MSE Supported

Precast Modular Gravity

Precast MSE Panel or Block

Cast-in-Place Reinforced Concrete

Precast Cantilevered

Precast Through-Tied



Figure 11: Precast Through-Tied Headwall



Figure 12: Precast MSE Panel Headwall



Figure 13: Precast Modular Gravity Headwall



Figure 14: Precast Cantilevered Headwall



Figure 15: Precast MSE Block Headwall



Figure 16: Cast-in-Place Headwall

Headwall elements that utilize reinforced concrete (either precast or cast-in-place elements) should be inspected with methods appropriate for concrete. The headwalls systems that utilize FRP should be inspected in a manner similar to the methods described below for the GArch and GBeam.

Headwalls should be inspected for creep and excessive deflections. Comments should be recorded about any visually noticeable deviations: bulges, deformations, creep, or settlement.

Location and measurements should be recorded if possible. Plumbness can be measured with a digital level and bulges can be measured as deviation from a straight stringline.

For headwalls with exposed connections such as bolt heads or bearing plates, these elements should be inspected for snugness and possible deterioration.

The area where the headwall connects to the structure at the base should be examined. Observations regarding the condition of the connection should be recorded and photographed.

The inspection and repair methods for the pultruded composite headwall are the same as for the GArch and GBeam as described below.

Since the headwalls are more susceptible to UV exposure than the superstructure elements, FRP components of the headwall should be inspected more closely for fiber bloom. Fiber blooming occurs over time when the matrix material deteriorates, and the surface fibers are exposed through the face of the laminate creating an optically or tactically inconsistent surface texture. This is typically not a structural concern and can be quickly treated with the re-application of a surface coat of resin or paint. Another way this is addressed, is by using surface veils when making the laminate. These surface veils protect the structural layers below by providing a sacrificial coating similar to a galvanized or metalized coating on steel protects the material below. It is not uncommon for FRP components to experience color fading over time as well due to exposure to UV light. This is not a structural concern and should be distinguished from fiber blooming.

d) Superstructure

i. GArch System

SCC Concrete Filled FRP Arch Tubes

Inspection points for the SCC Concrete Filled FRP Tubes include the surface applied paint system and remaining mil thickness, surface bulging or blistering, cracking, or delamination of arch laminate surface. The surface of the tube may also be tested auditorily using a tap hammer to ensure no delamination within the composite or at the interface of the SCC concrete and FRP tube.

Corrugated FRP Decking

Inspection points include delamination or separation at decking joints between arches. Each bay between arches should be thoroughly inspected. Depending on the decking product chosen for the design different surface finishes are possible. Some bridges will have been constructed with a concrete overlay on the soil side of the deck and the FRP decking is not structural in these applications. The most common type of damage to look for on the FRP Decking is abrasions, scratches, or cracking. Check for exposed fibers or delamination.

The decking is a pultruded composite product and will have a more consistent surface appearance than the arches. It should be smooth and free of the types of damage listed for arches.

The repair methods for the pultruded composite decking are the same as for the arches as described below.

Shear Studs (Skewed structures over 15 degrees typically)

Inspection points include exposure of stud length between deck at arch surface.

The purpose of these studs is to ensure that the FRP Decking is working in composite action with the FRP Arches. It is not uncommon for the deck and arch to shift slightly during the backfilling sequence of the structure. This may cause some of the shear studs to slightly separate from the arch. If the shear studs continue to separate from the arch surface after the backfill sequence is complete, then composite action and diaphragm action of the deck may be limited. Document with photos and measurements to see if the separation has changed over time.

Precast Concrete Fascia

Precast Concrete fascia are nonstructural elements intended to aesthetically cover the interaction of the arch, decking, and headwall connection, but they also add a level of lateral protection to the upstream arches from debris flowing down stream.

Inspection of these units should be consistent with inspection of precast concrete and attention to the connection points into the arch should be considered, as well as end bearing on foundation and arch apex bearing at top center of the structure.

Some concrete fascia is cast in place and have differing types of concrete to arch interface and connection (e.g. doweled in rebar into arch prior to casting, epoxy anchored after casting, etc.). The contract drawings should be consulted for clarification of system installed and methods of attachment.

ii. *GBeam System*

GBeams

Inspection points for the GBeams include the visual inspection of the surface for bulging, blistering, cracking, or delamination of the laminate. The surface of the beam may also be tested auditorily using a tap hammer to ensure no delamination within the composite. GBeams are manufactured with a surfacing veil on the exterior of the laminate. It is important to distinguish any damage or degradation observed in this material as it is not a structural layer.

Concrete Decks (CIP, Precast Concrete Full Depth, Precast Concrete Partial Depth)

The deck condition should be inspected, rated, and coded in accordance with standard practice given NBIS; FHWA Recording and Coding Guide for the Structure Inventory and Appraisal of the Nation's Bridges. The Partial Depth Precast Concrete Deck is considered a stay-in-place form for the CIP portion above. Its condition and

rating may not impact the structural integrity of the CIP deck provided that the shear connection extends sufficiently into the CIP portion of the deck.

Shear Connections

The shear connection is the interface between the GBeam and the deck. This connection may be composed of steel or FRP bolts with or without an intentionally roughened top flange surface of the GBeam. The contract drawings should be consulted to determine which shear connection was utilized.

In projects where the surface of the top flange of the GBeam was smooth, it is assumed that the steel bolt is in shear and is bearing against the top flange. The area around the bolt should be inspected for bulging, blistering, cracking, or delamination of the laminate. Note any signs of corrosion of the steel bolt. Maintenance may include cleaning and applying a galvanized repair coating to the exposed surface of the bolt.

In projects where the surface of the top flange of the GBeam was intentionally roughened, it is assumed that the bolt is in tension and the shear force is carried by the ridges of the top flange and corresponding ridges within the concrete deck. In this instance the FRP bolts should be inspected for any signs of bulging, blistering, cracking, or delamination. If a steel bolt was used, note any signs of corrosion. Maintenance may include cleaning and applying a galvanized repair coating to the exposed surface of the bolt.

In some projects there may also be utility connections either by plates bolted to the web of the GBeam or an extension of the shear connection. The area around these connection points should be inspected for bulging, blistering, cracking, or delamination of the laminate.




Figure 17: Example GBeam Top Flange with Sinusoidal Roughening



Figure 18: Corresponding Concrete Roughened Surface

CLASSIFYING OBSERVATIONS

The following categories of damage or deterioration are expounded upon to give further instruction to bridge inspectors to help classify their field observations. All of the following categories are considered potential maintenance items and are repairable. A qualified composites technician should be involved in all repair work. ACMA Certified Composites Technicians (CCT) have the necessary expertise to repair any of the following categories. Damage beyond the extent of the following categories shall be considered serious and shall be assessed by a licensed Professional Engineer experienced in composites engineering. In most cases, even severe damage can be repaired following composites industry guidelines.

1. Surface Discoloration / Fading

Discoloration and fading are not structural issues on their own, but they can be indicators that there is potential damage. Some early GArch bridges utilized a sacrificial veil layer known as bleeder cloth which provides a resin-rich surface that protects the reinforcing fibers below. A number of projects have also utilized a UV-resistant paint or resin pigment; however, UV exposure may still cause color fading. Discoloration can indicate abrasion damage, which if significant could be cause for maintenance or repair.




Figure 19: Example of Fading and Discoloration after UV Exposure

2. FRP Fiber Exposure and Abrasion

Typically, abrasion or fiber exposure is a result of improper handling or storage of materials prior to installation. Abrasion damage can be the result of exposure to water or other non-aggressive, but persistent physical contact. Abrasion that affects only the protective resin coat with no exposure of fibers is non-structural and can be repaired by recoating with a UV-resistant resin coat. If the source of abrasion is identified and cannot be avoided the composite should be coated with a resin with abrasion resistant fillers. A reinforcement or additional veil layer may be added for additional protection. If exposed fibers are left untreated, they can form into cracks or delamination over time with exposure to freeze-thaw cycles or moisture absorption. A simple repair of recoating the fibers with resin should alleviate future concerns.



Figure 20: Examples of Fiber Exposure or Abrasion

3. Delamination

These can be small single layer external blemishes caused by high impact small projectiles or hand tools or larger area encompassing deeper multi-layer separations caused by higher momentum carry loads (e.g. over height loads carried by over the road trucking and freight carriers). Classifying these types of material defects can be done by visual inspection augmented with auditory tap testing. Delamination can be a result of an internal void space continuing to expand and may be difficult to see as it may not always migrate to the surface. Auditory tap testing can quickly determine if a void or delamination is present beneath the surface, but the extent of depth may require the use of ultrasonic technology, infrared thermography, or ground penetrating radar. Signal penetrating equipment and technologies such as these typically require special training that is material specific.



Figure 21: Example of Delamination around a Drilled Hole

4. Subsurface Scratches

Scratches can occur from multiple sources such as high velocity water flow carrying floating or suspended debris such as tree branches or ice, improper material handling or storage, improper construction sequence leading to overstress, or non-natural causes like vandalism. Subsurface scratch damage differs from abrasion and fiber exposure in that the fibers are typically damaged.

Any damage to the fibers represents structural damage. Since composites are a mixture of many fibers and a matrix binder, oftentimes minor scratches are simply repaired by recoating with resin. Any damage larger than one square inch in size should be inspected closely to determine the extent of damage. Damage affecting a significant amount of the fibers should be repaired with additional fiber reinforcement using industry standards with materials equal to or better than the fibers that have been damaged. The repair method will depend on the severity and extent of damage to the fibers, but all work performed should be done by a Certified Composites Technician.



Figure 22: Examples of Subsurface Scratching

5. Laminate Penetration and Gouges

Large laminate penetrations and gouges that extend through the thickness of the laminate represent severe damage and should be repaired immediately by a Certified Composite Technician. Any penetration through the entire laminate larger than 1" in square should be

repaired with additional fiber reinforcement. Certain penetrations have been designed into the laminate such as holes for utility connections, vent or drainage holes, or holes for shear bolts. These laminate penetrations are not structurally damaging as they were planned during the design, but they should be inspected visually to ensure no bulging, delamination, scratching, or fiber exposure.

In the GArch system, if the damage resulted in the loss of concrete the void space must be filled with resin or grout.

GBeam laminates are similar in material to GArch laminates, but typically much thicker. For example, an arch may contain as few as two layers and have a laminate thickness around 0.10" and as many as five layers with a total laminate thickness around 0.25". GBeams vary in thickness from bottom flange to web to top flange and are topped over with but not filled with concrete. The laminate thickness of the GBeam can be as little as 0.50" thick to over 2" thick solid FRP. The laminates for the GBeam typically consist of a combination of C-FRP and G-FRP layering. The webs consist of a layer of PET Foam Core and G-FRP biaxial face sheets anywhere from 0.25" thick to 0.50" thick, meaning that the total web thickness can be anywhere from 1.00" to 2.50" thick.



Figure 23: Example of Laminate Penetration



Figure 24: Example of Laminate Gouging

6. Cracking

Cracking may occur from impacts from vehicles, in-stream debris, or improper storage and handling. Cracking differs from delamination and subsurface scratching in that it is typically through-thickness and over a larger area. Cracking also differs from gouges or penetrations in that the cracking is usually dispersed to a greater area and not concentrated like a gouge or penetration.

It is also possible that cracking may appear in areas with high resin content, or resin rich areas, where fiber volume fraction is low, and area may be locally brittle. The bottom radius of the GBeam where the webs transition into the bottom flange is a commonly resin rich area. Cracks in areas that have low fiber volume fraction are not as concerning as those in high fiber volume fraction. In all cases, cracks should be repaired with additional fiber reinforcement using industry standards with materials equal to or better than the fibers that have been damaged. This work should be performed by a CCT.

7. Bulging or Blistering

Blistering or bulging is common in FRP members that utilize a gelcoat or painted surface finish. Blistering occurs when moisture gets trapped between the laminate and the surface coating. These blisters are not likely to cause structural concerns but are potential sources for future issues if the bridge member is located in an environment that experiences freeze-thaw cycles. Blisters should be removed and sanded flush with the surrounding area and recoated with a surface coat of resin or paint.




Figure 25: Example of Blistering or Bulging

INSPECTION METHODS

1. Visual Inspection

Visual Inspection is the primary means of evaluating FRP members for damage or deficiencies. Visual inspection can be performed with a drone or high-resolution camera in areas that are difficult to access. It may be helpful to have a flashlight, tape measure, feeler gage set, and magnifying glass to aid in visual inspection. Any areas of potential damage should be marked, classified, documented, and evaluated to see if repair is necessary.

2. Non-Destructive Evaluation

a) Tap Test

This test consists of tapping the FRP with a large coin or small tap hammer and listening for a difference in sound. Clear, sharp ringing sound indicates a laminate that is sound and free of defect. If the sound is dull or hollow, that usually indicates either a delamination or void under the surface. It is important to review the contract plans prior to auditory tap testing to distinguish between potential voids and areas of the laminate that contain foam core. It is possible to mistake the foam core material as a void within the laminate. The feel of the impact can also indicate whether the material below is free of defect. If the material rebounds the impact well; it indicates that the material is free of void or delamination. If the rebound is lessened or deadened, it usually indicates that the material below is not sound or free of defects. Further NDE can then be focused on these areas.

b) Ground Penetrating Radar

Ground Penetrating Radar utilizes high frequency radio waves and can be used for determining subsurface characteristics of FRP or FRP to concrete interface to check for disbands or voids between materials. Typically, GPR is calibrated to the material because each material exhibits a different response to the electromagnetic waves due to differing permittivity of materials. This inspection method is gaining popularity in FRP inspection, but still requires large equipment and specialized training. It may be difficult to get large equipment to the areas in need of further inspection.

c) Ultrasonic

Ultrasonic testing is similar to GPR in that it uses high frequency sound waves to analyze the material, but a key advantage is the equipment can be handheld. This allows for a more localized surface and subsurface examination of FRP components. This technology can be used to determine delamination as well as subsurface cracking given the right resolution. The ultrasonic unit and transducer and may require a couplant gel. The inspector will need UT training on the equipment being utilized and will need to understand the wave characteristics of FRP materials as the response is different from traditional materials. Additionally, differences in the laminate architecture will produce varied readings, for example the bottom flange of a GBeam typically is made up of both carbon and glass reinforcing layers.



Figure 26 Ultrasonic Testing Equipment with Handheld Transducer and Output Display

d) Infrared Thermography

Infrared thermography involves applying an external heat source to the FRP material and utilizing an infrared imaging sensor to observe and record any gradient in the material. High density material will absorb heat and take longer to heat up but will retain the heat longer than low density materials. This change in temperature gradient can identify areas of delamination, cracking, presence of moisture, or voids and requires relatively little training to interpret results.




Figure 27 Infrared Thermography Schematic




Figure 28 Heat Map Display Indicating Temperature Differential at the Sample Surface

MAINTENANCE

1. Preventative Maintenance

One of the advantages of FRP materials is that they are corrosion resistant. However, like most structures they are not immune to impact damage or other forms of weakening from exposure to harsh environments if not monitored and maintained properly. Prior to determining if preventative maintenance is required, the FRP may need to be cleaned thoroughly.

A pressure washer is excellent for removing most types of soil or staining on FRP surfaces. To prevent damaging the FRP, the pressure washer should not exceed 2000 psi. When washing, keep the spray tip at least 12 inches away from the FRP.

A damp cloth, broom, or compressed air will remove most light to moderate dust or soil. Wipe, scrub, or blow off the dust.

Soap and water along with rags, a soft bristle brush, or a broom can be used to remove slightly heavier soil. Common household mild detergents should be used. Apply the soap and water then scrub. Rinse with clean water.

Preventative maintenance is expected to be repair that does not constitute a structural repair. This may include recoating the surface finish with resin or paint if fading or discoloration is present, repairing blistering, exposed fibers, abrasion, or minor scratches with resin. Preventative maintenance does not require special training or certification.

2. Minor Repairs

A minor repair is classified as a delamination, subsurface scratch, penetration, gouge, or surface crack that does not extend more than half the depth of the laminate and does not require engineering of the repair. The repair should be performed by a CCT. ACMA can provide a list of certified individuals and companies that have the necessary expertise to repair minor damage.

The procedure for minor repairs involves removing, or scarfing out, damaged material until undamaged laminate is found. As material is being removed, care should be taken to not extend the area that is damaged, and the direction of the reinforcement fabric should be noted. The repair area is then determined by tapering the removed material at a slope of 30:1 in all directions. For example, if a laminate is 1.0" thick and has a gouge that extend 0.25" into the laminate, the material at the gouge would be removed to just over 0.25" deep. Then the surrounding material would then be removed at a taper over a length of 7.5" to the full thickness of the laminate. The repair area would then be repaired with equal or better material cut to fit the tapered area and placed in the same orientation as the existing material. The repair method may be wet layup or vacuum infusion depending on the difficulty for access and extend of damage.

The Project Layup Schedule provided with the Quality Control Report should be consulted for specific reinforcement properties, for example one layer may be a Vectorply vendor nomenclature EBX-2400 which is a 24 ounce per square yard +/-45 glass fiber reinforcement, while the next layer may be Hexcel vendor nomenclature FCIM321 indicating a 24K tow carbon fiber reinforcement 595 grams per square meter oriented in the "0" direction or "UNI" direction which is the longitudinal direction of the girder. The layup schedule specifies the material as it is placed into the mold during production of the girder prior to vacuum infusion. The material as shown in the layup schedule is numbered from 1 to the total number of layers placed into the mold, where layer number 1 is the outermost layer as viewed from the outside surface of the

girder. Each successive layer is placed inside the previously numbered layer until the final layer is placed being the innermost layer number or the last number on the layup schedule.



Figure 29: Wet Layup Process




Figure 30: Example of Repair Mapping

3. Major Repairs

A major repair is classified as a delamination, subsurface scratch, penetration, gouge, or surface crack that extends more than half the depth of the laminate and requires engineering of the

repair. The repair should be performed by a CCT. ACMA can provide a list of certified individuals and companies that have the necessary expertise to repair major damage.

The procedure for major repairs involves removing, or scarfing out, damaged material until undamaged laminate is found. As material is being removed, care should be taken to not extend the area that is damaged, and the direction of the reinforcement fabric should be noted. The repair area is then determined by engineering design and may need to be larger than 30:1 or utilize specific materials. Once the repair area is engineered, the CCT would be provided with a laminate schedule and material specification to carry out the repair. The repair method may be wet layup or vacuum infusion depending on the difficulty for access, extend of damage, and quality of repair method.




Figure 31: Major Repair Preparation and Material Removal




Figure 32: Repair Layup Following Material and Layer Specifications



Figure 33: Repair Infusion



Figure 34: Completed Major Repair

USEFUL RESOURCES

- 1) *Bridge Inspector's Reference Manual* (BIRM), U.S. Department of Transportation – Federal Highway Administration, National Highway Institute, Publication No. FHWA NHI 12-049 December, 2012 <https://www.fhwa.dot.gov/bridge/nbis/pubs/nhi12049.pdf>
- 2) *Composite Materials Handbook, Volume 3 Polymer Matrix Composites Materials Usage Design, and Analysis* <https://www.sae.org/publications/books/content/r-424/>
- 3) Lee County Port Authority, Skyplex Boulevard Bridge Inspection
- 4) Highway Bridge Inspection Report, McGee Bridge, Anson, ME
- 5) PennDOT Bridge Maintenance Manual
<https://www.dot.state.pa.us/public/PubsForms/Publications/PUB%2055.pdf>
- 6) PennDOT Bridge Safety Inspection Manual
<https://www.dot.state.pa.us/public/PubsForms/Publications/PUB%20238.pdf>
- 7) Link to American Composites Manufacturers Association ACME <https://acmanet.org/>
- 8) *Field Inspection of In-Service FRP Bridge Decks*, National Cooperative Highway Research Program (NCHRP) Report 564, 2006 <http://www.trb.org/Publications/Blurbs/156715.aspx>

Highway Bridge Inspection Report

BR# 3171

TIDE MILL NO. 2

US 1

Over

CRANE MILL STREAM

Town:

Edmunds Twp



Inspection Date: 08/13/2020
7:36:00 PM

Inspected By: Harris, Steve


Inspection Type(s): Routine

Inspector: Steve Harris
Inspection Date: 08/13/2020

Structure Number: 3171
Facility Carried: US 1

Highway Bridge Inspection Report

Location Map



Latitude: 44.83005
Longitude: -67.16227

National Bridge Inventory

Status: 0 - ND

Bridge Name: TIDE MILL NO. 2

Sufficiency Rating: 80.3

Inspections

(90) INSPECTION DATE	& (91) DESIGNATED INSPECTION FREQUENCY	24	08/13/2020
(92) CRITICAL FEATURE INSPECTION	& (93) CFI DATE		
(92A) FRACTURE CRITICAL DETAIL		N	
(92B) UNDERWATER INSPECTION		N	
(92C) OTHER SPECIAL INSPECTION		N	

Identification

(1) STATE CODE	231 - Maine
(8) STRUCTURE NUMBER	3171
(5) INVENTORY ROUTE	
(5A) RECORD TYPE	1: Route carried "on" the structure
(5B) ROUTE SIGNING PREFIX	3 - STATE HIGHWAY
(5C) DESIGNATED LEVEL OF SERVICE	1 - MAINLINE
(5) INVENTORY ROUTE	1
(5) INVENTORY ROUTE	0 - NOT APPLICABLE
(2) HIGHWAY AGENCY DISTRICT	04 - Eastern
(3) COUNTY CODE	029 Washington
(4) PLACE CODE	22750
(6) FEATURES INTERSECTED	CRANE MILL STREAM
(7) FACILITY CARRIED	US 1
(9) LOCATION	2 MI. N.E. WHITING
(11) MILEPOINT	275.821
(12) BASE HIGHWAY NETWORK	Inventory Route is on the Base Network
(13) LRS INVENTORY ROUTE, SUBROUTE	
(13A) LRS INVENTORY ROUTE	000000001X
(13B) SUBROUTE NUMBER	00
(16) LATITUDE	44.83005
(17) LONGITUDE	-67.16227
(98A) BORDER BRIDGE CODE	
(98B) PERCENT RESPONSIBILITY	0
(99) BORDER BRIDGE STRUCT NO.	n/a

Structure Type and Material

(43) STRUCTURE TYPE, MAIN	
(43A) KIND OF MATERIAL/DESIGN	1 - Concrete
(43B) TYPE OF DESIGN/CONSTR	19 - Culvert (includes frame culverts)
(44) STRUCTURE TYPE, APPROACH SPANS	
(44A) KIND OF MATERIAL/DESIGN	0 - Other
(44B) TYPE OF DESIGN/CONSTRUCTION	00 - Other
(45) NUMBER OF SPANS IN MAIN UNIT	1
(46) NUMBER OF APPROACH SPANS	0
(107) DECK STRUCTURE TYPE	N - Not Applicable
(108) WEARING SURFACE/PROTECTIVE SYSTEMS	
(108A) WEARING SURFACE	N - NA
(108B) DECK MEMBRANE	N - NA
(108C) DECK PROTECTION	N - NA

Age of Service

(27) YEAR BUILT	2016
(106) YEAR RECONSTRUCTED	0
(42) TYPE OF SERVICE	
(42A) TYPE OF SERVICE ON BRIDGE	1 - Highway
(42B) TYPE OF SERVICE UNDER BRIDGE	5 - Waterway
(28) LANES	
(28A) LANES ON THE STRUCTURE	02
(28B) LANES UNDER THE STRUCTURE	00
(29) AVERAGE DAILY TRAFFIC	1546
(30) YEAR OF AVERAGE DAILY TRAFFIC	2016
(109) AVERAGE DAILY TRUCK TRAFFIC	5
(19) BYPASS DETOUR LENGTH	100

Geometric Data

(48) LENGTH OF MAXIMUM SPAN (ft.)	40
(49) STRUCTURE LENGTH (ft.)	60
(50) CURB/SIDEWALK WIDTHS	
(50A) LEFT CURB SIDEWALK (ft.)	00
(50B) RIGHT CURB SIDEWALK (ft.)	00
(51) BRDG RDWY WIDTH CURB-TO-CURB (ft.)	0000
(52) DECK WIDTH, OUT-TO-OUT (ft.)	0000
(32) APPROACH ROADWAY WIDTH (ft.)	29.0
(33) BRIDGE MEDIAN	0 - No median
(34) SKEW (deg.)	0
(35) STRUCTURE FLARED	0 - No flare
(10) INV RTE, MIN VERT CLEARANCE (ft.)	327.76
(47) TOTAL HORIZONTAL CLEARANCE (ft.)	23.0
(53) VERTICAL CLEARANCE OVER BRIDGE ROADWAY (ft.)	327.76
(54) MIN VERTICAL UNDERCLEARANCE	
(54A) REFERENCE FEATURE	N - Feature not a highway or railroad
(54B) MIN VERTICAL UNDERCLEASENCE (ft.)	0
(55) MIN LATERAL UNDER CLEARANCE RIGHT	
(55A) REFERENCE FEATURE	N - Feature not a highway or railroad
(55B) MIN LATERAL UNDER CLEARANCE RIGHT (ft.)	327.76
(56) MIN LATERAL UNDER CLEARANCE (ft.)	99.9

Classification

(112) NBIS BRIDGE LENGTH	Yes
(104) HIGHWAY SYSTEM OF THE INVENTORY ROUTE	0 - Structure/Route is NOT on NHS
(26) FUNCTIONAL CLASSIFICATION OF INVENTORY ROUTE	06 - Rural - Minor Arterial
(100) STRAHNET HIGHWAY DESIGNATION	Not a STRAHNET route
(101) PARALLEL STRUCTURE DESIGNATION	N - No parallel structure
(102) DIRECTION OF TRAFFIC	2-way traffic
(103) TEMP STRUCTURE	
(105) FEDERAL LANDS HIGHWAYS	Not Applicable
(110) DESIGNATED NATIONAL NETWORK	Inventory route not on network
(20) TOLL	3 - On Free Road
(21) MAINTENANCE RESPONSIBILITY	01 - State Highway Agency
(22) OWNER	01 - State Highway Agency
(37) HISTORICAL SIGNIFICANCE	5 - Not eligible

Condition

(58) DECK	N - Not Applicable
(59) SUPERSTRUCTURE	N - Not Applicable
(60) SUBSTRUCTURE	N - Not Applicable
(61) CHANNEL & CHANNEL PROTECTION	9 - No noticeable deficiencies
(62) CULVERT	8 - No noticeable or noteworthy deficiencies

Load Rating and Posting

(31) DESIGN LOAD	B - Greater than HL 93
(63) METHOD USED TO DETERMINE OPERATING RATING	8 - Load and Resistance Factor Rating (LRFR) rating report by rating factor (RF) method using HL-93 loadings.
(64) OPERATING RATING	1.32
(65) METHOD USED TO DETERMINE INVENTORY RATING	8 - Load and Resistance Factor Rating (LRFR) rating report by rating factor (RF) method using HL-93 loadings.
(66) INVENTORY RATING	1.02
(70) BRIDGE POSTING	5 - Equal to or above legal loads
(41) STRUCTURE OPEN/POSTED/CLOSED	A - Open

Appraisal

(67) STRUCTURAL EVALUATION	8
(68) DECK GEOMETRY	N
(69) UNDERCLEARANCES, VERTICAL & HORIZONTAL	N
(71) WATERWAY ADEQUACY	8 - Bridge Above Approaches
(72) APPROACH ROADWAY ALIGNMENT	8 - Equal to present desirable criteria
(36) TRAFFIC SAFETY FEATURE	
36A) BRIDGE RAILINGS:	0 - Does not meet acceptable standards/safety feature is required
36B) TRANSITIONS:	0 - Does not meet acceptable standards/safety feature is required
36C) APPROACH GUARDRAIL	0 - Does not meet acceptable standards/safety feature is required

36D) APPROACH GUARDRAIL ENDS
(113) SCOUR CRITICAL BRIDGES

0 - Does not meet acceptable standards/safety feature is required
8 - Stable for scour conditions

Proposed Improvements

(75) TYPE OF WORK	
(75A) TYPE OF WORK PROPOSED	
(75B) WORK DONE BY	
(76) LENGTH OF STRUCTURE IMPROVEMENT (ft.)	
(94) BRIDGE IMPROVEMENT COST (\$K)	
(95) ROADWAY IMPROVEMENT COST (\$K)	
(96) TOTAL PROJECT COST	
(97) YEAR OF IMPROVEMENT COST ESTIMATE	
(114) FUTURE ADT	2319
(115) YEAR OF FUTURE ADT	2036

Navigation Data

(38) NAVIGATION CONTROL	0 - No navigation control on waterway (bridge permit not required)
(111) PIER OR ABUTMENT PROTECTION	
(39) NAV VERT CLEARANCE	0
(116) MIN NAVIGATION VERT CLEARANCE, VERT LIFT BRIDGE	0
(40) NAV HORIZONTAL CLEARANCE	0

Inspection Notes

Structure Number: 3171

Town: Edmunds Twp

Structure Name: TIDE MILL NO. 2

Structure Notes

2016 Single span buried filled tube arches on concrete footings with corrugated composite deck

Wearing Surface

Deck **NBI Item 58:** N

Superstructure **NBI Item 59:** N

Substructure **NBI Item 60:** N

Culvert **NBI Item 62:** 8

Single span buried filled tube arches on concrete footings with corrugated composite deck.
Deck panels are leaking with resulting staining on tube arches and footings.
No cracking, delaminating or spalling footings.
Concrete retaining head walls with no issues noted.
Large rip-rap in angular and unstable at this time but there is no banking erosion

Channel **NBI Item 61:** 9

Other

Special Inspection

Monitoring

Pontis Notes

Inspector: Steve Harris
Inspection Date: 08/13/2020

Structure Number: 3171
Facility Carried: US 1

Highway Bridge Inspection Report

Element Inspection

	Environment	Total Quantity	Units	Condition State 1	Condition State 2	Condition State 3	Condition State 4
243 - Other Culvert	3 - Mod.	60	ft.	55	5	0	0
824 - Prefabricated Concrete Wall	3 - Mod.	160	ft.	160	0	0	0

Over Limit Report

Bridge #: 3171
 Bridge Name: TIDE MILL NO. 2
 Owner: 01 - State Highway Agency
 Co-Owner: N Not applicable
 Region: 04 - Eastern

Town1: Edmunds Twp
 Town2:
 Maintainer: 01 - State Highway Agency
 Co-Maintainer: N Not applicable

Vertical Clearance - Under		<i>Left, Center, and Right is based on the direction of travel</i>					
<u>Roadway - Heading North or East</u>		Actual Heights in Feet-Inches			Posted	Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>		<u>Deficient Sign</u>	
Main:	<input type="text" value="CRANE MILL STREAM"/>	-	-	-	<input type="checkbox"/> Main	-	
Other:	<input type="text"/>	-	-	-	<input type="checkbox"/> Other	-	
	Ramps:	-	-	-	<input type="checkbox"/> Ramp	-	
<u>Roadway - Heading South or West</u>		Actual Heights in Feet-Inches			Posted	Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>		<u>Deficient Sign</u>	
Main:	<input type="text" value="CRANE MILL STREAM"/>	-	-	-	<input type="checkbox"/> Main	-	
Other:	<input type="text"/>	-	-	-	<input type="checkbox"/> Other	-	
	Ramps:	-	-	-	<input type="checkbox"/> Ramp	-	

Vertical Clearance - Portal		Roadway: <input type="text" value="US 1"/>					
<u>Heading North or East</u>		Actual Heights in Feet-Inches			Posted	Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>		<u>Deficient Sign</u>	
		-	-	-	<input type="checkbox"/> Portal	-	
<u>Heading South or West</u>		Actual Heights in Feet-Inches			Posted	Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>		<u>Deficient Sign</u>	
		-	-	-	<input type="checkbox"/> Portal	-	

Permitting		<u>Pointer</u>	<input type="checkbox"/> Red Flag Comments
Heading North Height:	-		<div style="border: 1px solid black; height: 100%;"></div>
Heading South Height:	-		
Left Ramp Height:	-		
Right Ramp Height:	-		
Portal North Height:	-	2050162-BRDG	
Portal South Height:	-	2050162-BRDG	
Other Road Height:	-		
Bridge Width:	0000 ft		
Roadway Width:	29.0 ft		
Underclearance heights are signed if less than 14 ft 6 in Check with Maine Turnpike Authority for load heights over 13 ft 6 in Always check 511			

Load Restrictions			
Posted	False	tons	Date posted:
Posted One Truck at aTime			
Posted for 4 axle only			
Operating Load Rating	1.32		
Permit Load Ratings		axles	
		axles	
		axles	

Underwater Dive Inspection Report

Structure Number: 3171
Town 1: 29804 - Edmunds Twp
Division: Ellsworth
Location: 2 MI. N.E. WHITING
Tide Information:
Dive Entry Location:
Scour:
Comments/Hazards:

Bridge Name: TIDE MILL NO. 2
Town 2:
DiveID: 2930

Tidal:

Photos:

Streambed Description:

Channel Description:

Substructure Description:

Inspection Team:

Role:

Dive Conditions:

Time: Entry: AM/PM

Time: Exit: AM/PM

Water Temp:

Visibility (ft):

Max Depth (ft):

Current:

Weather:

Underwater Inspection Date:

Channel Condition:

Substr/Culvert Condition:

Inspection Cycle:

Ratings Comments:

Highway Bridge Inspection Report

Pictures



PHOTO 1

Description Roadway looking South



PHOTO 2

Description Roadway pavement above Bridge

Highway Bridge Inspection Report

Pictures



PHOTO 3

Description Guard Rail View



PHOTO 5

Description Barrel View looking West

Highway Bridge Inspection Report

Pictures



PHOTO 6

Description South Footing View



PHOTO 7

Description North Footing View

Highway Bridge Inspection Report

Pictures



PHOTO 8

Description West Composite Tube - Staining on bottom



PHOTO 9

Description Interior tubes - Staining at bottom

Highway Bridge Inspection Report

Pictures



PHOTO 10

Description Staining of East Tube

Maintenance Work Items

Structure Number: 3171

Structure Name: TIDE MILL NO. 2

Town: 29804

Owner: Harris, Steve

Type	Work Item	Priority	Notes
------	-----------	----------	-------

MaineDOT NBIS Bridge Safety Inspection JSA

Structure Number: 3171

Inspector: Harris, Steve

Structure Name: TIDE MILL NO. 2

Team Lead: Steve Harris

Town: Edmunds Twp

Additional Team Members/Visitors:

- | | |
|-----|-----|
| 1.) | 6.) |
| 2.) | 7.) |
| 3.) | 8.) |
| 4.) | 9.) |
| 5.) | |

Job being performed:

Bridge Inspection

Potential Hazard:

- Exposure to traffic

Potential Hazard:

- Steep slopes and uneven working areas
(rip rap, mud, loose fill, etc)

Potential Hazard:

- Chipped Concrete or Steel (hand tools only)

Potential Hazard:

- 6' Vertical drops

Potential Hazard:

- Water Hazards

- Water depth under 1 foot
- Water depth 1 to 4 feet
- Water depth over 4 feet
- Water flow calm/slow moving
- Water flow visible/not rapid
- Water flow rapid with some short falls
- Tidal Water

Potential Hazard:

-

Controls:

- Parked off road with strobe
- Less than 1 hour on bridge
- Wear standard reflective clothing and hard hat
- Spotter Traffic Control Crew

Controls:

- Wear appropriate, prudent footwear
- Rope or fall protection

Controls:

- Wear appropriate, prudent eye/hand protection

Controls:

- Stay away from areas

Controls:

- Evaluate Water Hazard conditions
- Use/Wear appropriate PPE
- Buddy System

Controls:

-

Insects, Poison Ivy, or other environmental hazards

Potential Hazard:

Lead paint and Avian excrement

Potential Hazard:

Heavy Manual Lifting

Potential Hazard:

DCS, Lung Expansion

Potential Hazard:

Entanglement U/W

Potential Hazard:

Boat Traffic

Potential Hazard:

Cold Water

Potential Hazard:

Live Boating

Other Potential Hazards:

Loose rip rap

Safety Equipment Required:

Apply insect repellent and/or sunscreen

Protect skin with appropriate, prudent clothing

Controls:

Wear gloves, do not scrape

Controls:

Ask for assistance in donning dive gear, lifting equipment

Controls:

Ascend slowly, use computers, Safety Stops (15' mark for 3 min.)

Controls:

Use knife, Comm gear

Controls:

Fly Dive Flag, use spotter, contact bridge on Chan. 13

Controls:

Use adequate dry suit underwear for water temperature

Controls:

Keep track of divers, avoid powering during drop-off/pick-up

Other Controls:

Ensure footing

Emergency Action Plan:

Hard hat

- Vest
- Glasses
- Gloves
- PFD
- Rain Gear
- Bug Spray

Sunscreen

- First Aid
- O2
- AED
- Comm Gear
- Cell Phone
- Boat

Throw Ring

- Throw Rope
- Positioning Device

Call 911

- First Aid Kit
- Fall Rescue Plan
- Water Rescue Plan
- Dan 1-919-684-9111
- USCG 741-5465

Other Safety Equipment:

Other Emergency Action Plan:

I certify that the MaineDOT NBIS Bridge Safety Inspection JSA has been completed according to all proper procedures required by the Maine Department of Transportation.

Complete Steve Harris

Bridge Components

Bridge #: 3171
 Bridge Name: TIDE MILL NO. 2
 Owner: 01 - State Highway Agency
 Co-Owner: N Not applicable
 Region: 04 - Eastern

Town1: Edmunds Twp
 Town2:
 Maintainer: 01 - State Highway Agency
 Co-Maintainer: N Not applicable

Deck

<u>Joint Seal Type/MFG:</u>	<u>Joint Types:</u>	<u>Joint HDR Mat:</u>	<u>Other:</u>	<u>Rebar Type:</u>
<input type="checkbox"/> Emseal <input type="checkbox"/> V Seal <input type="checkbox"/> Watson Bowman <input type="checkbox"/> Hot Rubber <input type="checkbox"/> Pour-in-Place <input type="checkbox"/> DS Brown	<input type="checkbox"/> Finger <input type="checkbox"/> Asphaltic Plug <input type="checkbox"/> Compression <input type="checkbox"/> Modular <input type="checkbox"/> Gland <input type="checkbox"/> Waybo Crete	<input type="checkbox"/> Sliding <input type="checkbox"/> Transflex <input type="checkbox"/> Open	<input type="checkbox"/> Concrete <input type="checkbox"/> Delcrete <input type="checkbox"/> Elastomeric <input type="checkbox"/> LP Concrete <input type="checkbox"/> Phoscrete <input type="checkbox"/> Plycrete	<input type="checkbox"/> Curtain <input type="checkbox"/> Troughs <input type="checkbox"/> Armor

Superstructure

<u>Left Side Rail:</u>			<u>Right Side Rail:</u>		
Material	Steel	<input type="checkbox"/> Retrofit	Material	Steel	<input type="checkbox"/> Retrofit
Shape	Rectangular	<input type="checkbox"/> Safety Walk	Shape	Rectangular	<input type="checkbox"/> Safety Walk
Attached To	Beam	<input type="checkbox"/> Pales	Attached To	Beam	<input type="checkbox"/> Pales
Number of Bars	2	<input type="checkbox"/> Snow Fence	Number of Bars	2	<input type="checkbox"/> Snow Fence
Extra Height	N		Extra Height	N	

<u>Bearing Type Quantity:</u>	<u>Fatigue Prone Detail:</u>	
<input type="checkbox"/> Disk <input type="checkbox"/> Pot <input type="checkbox"/> Roller	<input type="checkbox"/> Elastomeric <input type="checkbox"/> Rocker <input type="checkbox"/> Sliding Plate	<input type="checkbox"/> Narrow Cover Plate - Sq End Welded <input type="checkbox"/> Narrow Cover Plate - Sq End w/o Weld <input type="checkbox"/> Wide Cover Plate - Sq End Welded <input type="checkbox"/> Wide Cover Plate - Sq End w/o Weld <input type="checkbox"/> Lateral Connection Plate - Welded
<u>Other:</u> <input type="checkbox"/> Pin Quantity <input type="checkbox"/> Pin and Link Quantity		<input type="checkbox"/> Narrow Cover Plate - Tapered End Welded <input type="checkbox"/> Narrow Cover Plate - Tapered End w/o Weld <input type="checkbox"/> Longitudinal Stiffener - Welded with Radius <input type="checkbox"/> Longitudinal Stiffener - Welded w/o Radius <input type="checkbox"/> Hoan Detail

Substructure

<input type="checkbox"/> Pier Collars <input type="checkbox"/> Abutment Collars <input type="checkbox"/> Wood Piles <input type="checkbox"/> Steel Piles <input type="checkbox"/> Blocked Bridge	<u>Retaining Wall Type:</u> Precast Concrete Block Gravity
--	---

Other

Confined Space
 Bridge Lighting
 Cat Walk
 Navigational Lighting
 Signs Attached

General Notes

Bridge Preservation

Bridge #: 3171
 Bridge Name: TIDE MILL NO. 2
 Owner: 01 - State Highway Agency
 Co-Owner: N Not applicable
 Region: 04 - Eastern

Town1: Edmunds Twp
 Town2:
 Maintainer: 01 - State Highway Agency
 Co-Maintainer: N Not applicable

<p>Deck</p> <p><u>NBI Deck Information:</u></p> <p>Deck Type N - Not Applicable</p> <p>Deck Protection N - NA</p> <p>Membrane Type N - NA</p> <p style="text-align: right;"><u>Wearing Surface:</u></p> <p style="text-align: right;">Type N - NA</p> <p style="text-align: right;">Last Date</p> <p style="text-align: right;">Lifespan (Yrs)</p> <p style="text-align: right;">Next Date Est. 0</p> <p style="text-align: right;">Mill & Fill Date</p> <hr/> <p>Superstructure</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 33%;"><u>Beam Ends Paint:</u></td> <td style="width: 33%;"><u>Bearings Paint:</u></td> <td style="width: 33%;"><u>Bearings Lubrication:</u></td> </tr> <tr> <td>Last Date</td> <td>Last Date</td> <td>Last Date</td> </tr> <tr> <td>Next Date Est.</td> <td>Next Date Est.</td> <td>Next Date Est.</td> </tr> </table> <table style="width: 100%; border: none; margin-top: 10px;"> <tr> <td style="width: 33%;"><u>Beam Ends Fluid Film:</u></td> <td style="width: 33%;"><u>Bearings Fluid Film:</u></td> <td style="width: 33%;"><u>Treatment:</u></td> </tr> <tr> <td>Last Date</td> <td>Last Date</td> <td><input type="checkbox"/> Core 10</td> </tr> <tr> <td>Next Date Est.</td> <td>Next Date Est.</td> <td><input type="checkbox"/> Galvanized</td> </tr> <tr> <td></td> <td></td> <td><input type="checkbox"/> Metalized</td> </tr> </table> <hr/> <p>Substructure</p>	<u>Beam Ends Paint:</u>	<u>Bearings Paint:</u>	<u>Bearings Lubrication:</u>	Last Date	Last Date	Last Date	Next Date Est.	Next Date Est.	Next Date Est.	<u>Beam Ends Fluid Film:</u>	<u>Bearings Fluid Film:</u>	<u>Treatment:</u>	Last Date	Last Date	<input type="checkbox"/> Core 10	Next Date Est.	Next Date Est.	<input type="checkbox"/> Galvanized			<input type="checkbox"/> Metalized	<p>Common Preservation</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"><u>Paint Information:</u></td> <td style="width: 50%;"><u>Anodes:</u></td> </tr> <tr> <td>Type</td> <td><input type="checkbox"/> Installed</td> </tr> <tr> <td>Last Date</td> <td><input type="checkbox"/> Detached</td> </tr> <tr> <td>Lifespan (Yrs)</td> <td><input type="checkbox"/> Replace</td> </tr> <tr> <td>Next Date Est. 2002</td> <td></td> </tr> </table> <hr/> <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"><u>Concrete-Silane:</u></td> <td style="width: 50%;"><u>Washing:</u></td> </tr> <tr> <td>Last Date</td> <td><input type="checkbox"/> Required</td> </tr> <tr> <td>Next Date Est.</td> <td><input type="checkbox"/> UBIT</td> </tr> </table> <hr/> <p><u>Concrete-Linseed</u></p> <p>Last Date</p> <p>Next Date Est.</p> <p><input type="checkbox"/> Alkali-Silica reactivity</p>	<u>Paint Information:</u>	<u>Anodes:</u>	Type	<input type="checkbox"/> Installed	Last Date	<input type="checkbox"/> Detached	Lifespan (Yrs)	<input type="checkbox"/> Replace	Next Date Est. 2002		<u>Concrete-Silane:</u>	<u>Washing:</u>	Last Date	<input type="checkbox"/> Required	Next Date Est.	<input type="checkbox"/> UBIT
<u>Beam Ends Paint:</u>	<u>Bearings Paint:</u>	<u>Bearings Lubrication:</u>																																				
Last Date	Last Date	Last Date																																				
Next Date Est.	Next Date Est.	Next Date Est.																																				
<u>Beam Ends Fluid Film:</u>	<u>Bearings Fluid Film:</u>	<u>Treatment:</u>																																				
Last Date	Last Date	<input type="checkbox"/> Core 10																																				
Next Date Est.	Next Date Est.	<input type="checkbox"/> Galvanized																																				
		<input type="checkbox"/> Metalized																																				
<u>Paint Information:</u>	<u>Anodes:</u>																																					
Type	<input type="checkbox"/> Installed																																					
Last Date	<input type="checkbox"/> Detached																																					
Lifespan (Yrs)	<input type="checkbox"/> Replace																																					
Next Date Est. 2002																																						
<u>Concrete-Silane:</u>	<u>Washing:</u>																																					
Last Date	<input type="checkbox"/> Required																																					
Next Date Est.	<input type="checkbox"/> UBIT																																					
<p>General Notes</p> 																																						

BRIDGE RECORD



BRIDGE NUMBER: 124142
BRIDGE NAME: SKYPLEX BLVD BRIDGE

BRIDGE RECORD CONTENTS

- I. Inspection Reports - This section contains periodic bridge inspection reports, bridge repair work orders, and accident reports.
- II. Inventory – This section contained the following bridge information: photographs, location map, detailed data, history, load carrying capacity, inspection preparation, and drawings.
- III. Communications – This section contains correspondence such as letters, memorandums, and notices directly related to this bridge.

SECTION I
BRIDGE INSPECTION REPORTS

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection**

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV

BY: Marlin Engineering, Inc.	STRUCTURE NAME: SKYPLEX BLVD BRIDGE
OWNER: 25 Other Local Agencies	YEAR BUILT: 2020
MAINTAINED BY: 25 Other Local Agencies	SECTION NO.: 12 000 000
STRUCTURE TYPE: 0 Other - 11 Arch-Deck	MP: 0.000
LOCATION: 300 FT S/O CR-876	ROUTE: 00000
SERV. TYPE ON: 1 Highway	FACILITY CARRIED: SKYPLEX BLVD
SERV. TYPE UNDER: 5 Waterway	FEATURE INTERSECTED: ARTIFICIAL LAKE

 FUNCTIONALLY OBSOLETE STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Regular NBI

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 1/30/2020 UNDERWATER: N/A

SUFFICIENCY RATING: 95.8
HEALTH INDEX: 100

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV

BY: Marlin Engineering, Inc.
OWNER: 25 Other Local Agencies
MAINTAINED BY: 25 Other Local Agencies
STRUCTURE TYPE: 0 Other - 11 Arch-Deck
LOCATION: 300 FT S/O CR-876
SERV. TYPE ON: 1 Highway
SERV. TYPE UNDER: 5 Waterway

STRUCTURE NAME: SKYPLEX BLVD BRIDGE
YEAR BUILT: 2020
SECTION NO.: 12 000 000
MP: 0.000
ROUTE: 00000
FACILITY CARRIED: SKYPLEX BLVD
FEATURE INTERSECTED: ARTIFICIAL LAKE

- THIS BRIDGE CONTAINS FRACTURE CRITICAL COMPONENTS
THIS BRIDGE IS SCOUR CRITICAL
THIS REPORT IDENTIFIES DEFICIENCIES WHICH REQUIRE PROMPT CORRECTIVE ACTION
FUNCTIONALLY OBSOLETE
STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Regular NBI

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 1/30/2020 UNDERWATER: N/A

OVERALL NBI RATINGS:

DECK: N N/A (NBI) CHANNEL: 8 Protected
SUPERSTRUCTURE: 8 Very Good CULVERT: N N/A (NBI)
SUBSTRUCTURE: 8 Very Good SUFF. RATING: 95.8
PERF. RATING: Performance Rating Not applicable or not calculable. HEALTH INDEX: 100

FIELD PERSONNEL / TITLE / NUMBER:

INITIALS

Ryan, William - Bridge Inspector (CBI# 00497) (lead)
Jasper, Andrew - Bridge Inspection Technician

Blank lines for initials

REVIEWING BRIDGE INSPECTION SUPERVISOR:


Gassman, Edward - Struct Operations Manager (PE# 48513)

CONFIRMING REGISTERED PROFESSIONAL ENGINEER:

Fielding, Robert - Senior Project Engineer (PE #53156) Marlin Engineering, Inc.
1907 N US Highway 301, Suite 160-C
Certificate of Authorization #6104
Tampa Florida 33619

SIGNATURE:

DATE:



The official record of this package has been electronically signed and sealed by Robert A. Fielding, P.E. on the date adjacent to the seal as required by Rule 61G15-23.004, F.A.C.. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection**

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV

All Elements

MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	8290 / 3	Channel	1	100	0	.	0	.	0	.	1 (EA)

Element Inspection Notes:

8290/3 -

MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	8478 / 3	MSE Walls	328	100	0	.	0	.	0	.	328 ft

Element Inspection Notes:

8478/3 NOTE: This element represents the arch copings, all retaining walls and 30ft. past the angle break at all four corners of the structure.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	220 / 3	Re Conc Pile Cap/Ftg	228	100	0	.	0	.	0	.	228 ft

Element Inspection Notes:

220/3 NOTE: This element represents the footings and the 24 rebar tie-backs between footings at the arch ribs. Design plans show piling under each rib.

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	8396 / 3	Other Abutment Slope Protection	1920	100	0	.	0	.	0	.	1920 (SF)

Element Inspection Notes:

8396/3 NOTE: This element represents the rock rubble slope protection 30ft. east and west of the structure.

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	142 / 3	Other Arch	114	100	0	.	0	.	0	.	114 ft

Element Inspection Notes:

142/3 NOTE: This element represents the 24 concrete-filled fiber reinforced polymer (FRP) arches with corrugated fiber reinforced polymer decking between the arches. The top of the structure is covered by brick pavers and a median, and is earth filled.

CS1: The FRP corrugated decking and arches have areas of corrosion staining from an unknown source, primarily at the decking splices.

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
----------	----------	-------------	------	----	------	----	------	----	------	----	-------

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV



Photo 1 - Element 333/3 Other Bridge Railing

Gap in left approach sidewalk hand rail baseplate. Typical.

REPAIR RECOMMENDATION:

Repair gaps for approach sidewalk hand rail baseplates.

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV



Photo 2 - Element 333/3 Other Bridge Railing

Slack in 2nd hand rail cable from top for the right hand rail over arch.

REPAIR RECOMMENDATION:

Tighten 2nd hand rail cable from top for the right hand rail over arch.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection**

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV



Photo 3 - Inspection Notes

Protruding bolts at northeast pillar. Typical.

REPAIR RECOMMENDATION:
None.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Inspection**

Structure ID: 124142

DISTRICT: D1 - Bartow

INSPECTION DATE: 1/30/2020 TZAV



Photo 4 - Inspection Notes

Missing light fixture with exposed wires at northeast pillar.

REPAIR RECOMMENDATION:
Install light fixture at northeast pillar.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

Inspection/CIDR/Bridge Profile Report

REPORT ID: INSP005

Structure ID: 124142

CIDR

DATE PRINTED: 3/18/2020

Description

Structure Unit Identification

Bridge/Unit Key: 124142 1
 Structure Name: SKYPLEX BLVD BRIDGE
 Description: 32ft. x 9.5ft. ARCH BRIDGE
 Type: M - Main

Roadway Identification

NBI Structure No (8): 124142
 Position/Prefix (5): 1 - Route On Structure
 Kind Hwy (Rte Prefix): 8 Other (incl toll rds)
 Design Level of Service: 1 Mainline
 Route Number/Suffix: 00000 / 0 N/A (NBI)
 Feature Intersect (6): ARTIFICIAL LAKE
 Critical Facility: Not Defense-crit
 Facility Carried (7): SKYPLEX BLVD
 Mile Point (11): 0
 Latitude (16): 026d32'56.6" Long (17): 081d45'31.1"

Roadway Traffic and Accidents

Lanes (28): 4 Medians: 1 Speed: 35 mph
 ADT Class:
 Recent ADT (29): 2350 Year (30): 2020
 Future ADT (114): 2938 Year (115): 2040
 Truck % ADT (109): 3
 Detour Length (19): 1.1 mi
 Detour Speed: 35 mph
 Accident Count: Rate:

Roadway Classification

Nat. Hwy Sys (104): 0 Not on NHS
 National base Net (12): 0 - Not on Base Network
 LRS Inventory Rte (13a): 12 000 000 Sub Rte (13b): 00
 Functional Class (26): 19 Urban Local
 Federal Aid System: OFF
 Defense Hwy (100): 0 Not a STRAHNET hwy
 Direction of Traffic (102): 2 2-way traffic
 Emergency:

Roadway Clearances

Vertical (10): 99.99 ft Appr. Road (32): 58 ft
 Horiz. (47): 99.9 ft Roadway (51): 58 ft
 Truck Network (110): 0 Not part of natl netwo
 Toll Facility (20): 3 On free road
 Fed. Lands Hwy (105): 0 N/A (NBI)
 School Bus Route:
 Transit Route:

NBI Project Data

Proposed Work (075A):
 Work To Be Done By (075B): Unknown (NBI)
 Improvement Length (076): 0 ft

Improvement Cost (094):
 Roadway Improvement Cost (095):
 Total Cost (096):
 Year of Estimate (097):

NBI Rating

Channel (61): 8 Protected
 Deck (58): N N/A (NBI)
 Superstructure (59): 8 Very Good
 Substructure (60): 8 Very Good

Culvert (62): N N/A (NBI)
 Waterway (71): 8 Equal Desirable
 Unrepaired Spalls:
 Review Required:

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR/Bridge Profile Report

REPORT ID: INSP005

Structure ID: 124142

CIDR

DATE PRINTED: 3/19/2020

Structure Identification

Admin Area: Lee County
 District (2): D1 - Bartow
 County (3): (12)Lee
 Place Code (4): Fort Myers
 Location (9): 300 FT S/O CR-876
 Border Br St/Reg (98): Not Applicable (P) Share: 0 %
 Border Struct No (99):
 FIPS State/Region (1): 12 Florida Region 4-Atlanta
 NBIS Bridge Len (112): Y - Meets NBI Length
 Parallel Structure (101): No || bridge exists
 Temp. Structure (103): Not Applicable (P)
 Maint. Resp. (21): 25 Other Local Agencies
 Owner (22): 25 Other Local Agencies
 Historic Signif. (37): 5 Not eligible for NRHP

Structure Type and Material

Curb/Sidewalk (50): Left: 14.7 ft Right: 14.7 ft
 Bridge Median (33): 2 Closed Med w/o Barrier
 Main Span Material (43A): 0 Other
 Appr Span Material (44A): Not Applicable (P)
 Main Span Design (43B): 11 Arch-Deck
 Appr Span Design (44B): Not Applicable (P)

Appraisal

Structure Appraisal

Open/Posted/Closed (41): A Open, no restriction
 Deck Geometry (68): 5 Above Tolerable
 Underclearances (69): N Not applicable (NBI)
 Approach Alignment (72): 8-No Speed Red thru Curv
 Bridge Railings (36a): 0 Substandard
 Transitions (36b): 0 Substandard
 Approach Guardrail (36c): 0 Substandard
 Approach Guardrail Ends (36d): 0 Substandard
 Scour Critical (113): 8 Stable Above Footing

Minimum Vertical Clearance

Over Structure (53): 99.99 ft
 Under (reference) (54a): N Feature not hwy or RR
 Under (54b): 0 ft

Schedule

Current Inspection

Inspection Date: 01/30/2020
 Inspector: KNMEIWR - William Ryan
 Bridge Group: E1N92
 Alt. Bridge Group:
 Primary Type: Regular NBI
 Review Required:

Geometrics

Spans in Main Unit (45): 1
 Approach Spans (46): 0
 Length of Max Span (48): 34 ft
 Structure Length (49): 34 ft
 Total Length: 34 ft
 Deck Area: 3740 sqft
 Structure Flared (35): 0 No flare

Age and Service

Year Built (27): 2020
 Year Reconstructed (106): 0
 Type of Service On (42a): 1 Highway
 Under (42b): 5 Waterway
 Fracture Critical Details: Not Applicable

Deck Type and Material

Deck Width (52): 0 ft
 Skew (34): 0 deg
 Deck Type (107): 9 Other
 Surface (108): 9 Other
 Membrane: 0 None
 Deck Protection: 9 Other

Navigation Data

Navigation Control (38): Permit Not Required
 Nav Vertical Clr (39): 0 ft
 Nav Horizontal Clr (40): 0 ft
 Min Vert Lift Clr (116): 0 ft
 Pier Protection (111): Not Applicable (P)

NBI Condition Rating

Sufficiency Rating: 95.8
 Health Index: 100
 Structural Eval (67): 8 Equal Desirable Crit
 Deficiency: Not Deficient

Minimum Lateral Underclearance

Reference (55a): N Feature not hwy or RR
 Right Side (55b): 0 ft
 Left Side (56): 0 ft

Next Inspection Date Scheduled

NBI: 01/30/2022
 Element: 01/30/2022
 Fracture Critical:
 Underwater:
 Other/Special:
 Inventory Photo Update Due: 01/30/2030

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

Inspection/CIDR/Bridge Profile Report

REPORT ID: INSP005

Structure ID: 124142

CIDR

DATE PRINTED: 3/18/2020

Schedule Cont.

Inspection Types Performed

NBI Element Fracture Critical Underwater Other Special

Inspection Intervals Required (92) Frequency (92) Last Date (93) Inspection Resources

Fracture Critical	<input type="checkbox"/>	mos			Crew Hours: 3
Underwater	<input type="checkbox"/>	mos			Flagger Hours: 0
Other Special	<input type="checkbox"/>	mos			Helper Hours: 0
NBI		24 mos	(91)	01/30/2020 (90)	Snooper Hours: 0
					Special Crew Hours: 0
					Special Equip Hours: 0

Bridge Related

General Bridge Information

Parallel Bridge Seq:		Bridge Rail 1: Combination not defined
Channel Depth: 2.5 ft		Bridge Rail 2: Not applicable-No rail
Radio Frequency:		Electrical Devices: Roadway lighting only
Phone Number:		Culvert Type: Not applicable
Exception Date:		Maintenance Yard: Not FDOT Maintained
Exception Type:		FIHS ON / OFF: No Routes on FIHS
Accepted By Maint:		Previous Structure:
Warranty Expiration: 00/00/0000		2nd Previous Structure:
Performance Rating: Performance Rating Not applicable or not calculable.		Replacement Structure:

Permitted Utilities: Power Water Gas Fiber Optic Sewage Other

Bridge Load Rating Information

Inventory Type (065): 3 LRFR Load & Res. Fact	Inventory Rating (066): 36.4 tons
Operating Type (063): 3 LRFR Load & Res. Fact	Operating Rating (064): 47.2 tons
Original Design Load (031): HL 93	FL120 Permit Rating: 60.6 tons
Date: 01/18/2019	HS20/FL120 Max Span Rating: 60.6 tons
Initials: ZU	Dynamic Impact in Percent: 18 %
Load Rating Rev. Recom.: No	Governing Span Length: 32.0 ft
Load Rating Plans Status: Built	Minimum Span Length: 32.0 ft
	Distribution Method: Refined Analysis (RA)

Load Rating Notes:

LEGAL LOADS

SU2: -1.0 tons
 SU3: -1.0 tons
 SU4: -1.0 tons
 C3: -1.0 tons
 C4: -1.0 tons
 C5: -1.0 tons
 ST5: -1.0 tons

Posting (070): 5 At/Above Legal Loads
 Open/Posted/Closed (041): A Open, no restriction

POSTING

Recom. SU Posting: 99 tons
 Recom. C Posting: 99 tons
 Recom. ST5 Posting: 99 tons
 Actual SU Posting: 99 tons
 Actual C Posting: 99 tons
 Actual ST5 Posting: 99 tons
 Actual Blanket Posting: 99 tons
 Emergency Vehicle: 1 EV inapplicable

FLOOR BEAM (FB)

FB Present: No
 FB Span Length, Gov: 0.0 ft
 FB Spacing, Gov: 0.0 ft
 FB OPR Rating: 0.0 tons
 FB SU4 OPR Rating: 0.0 tons
 FB FL120 Rating: 0.0 tons

SEGMENTAL (SEG)

SEG Wing-Span: -1.0 ft
 SEG Web-to-Web Span: -1.0 ft
 SEG Transverse HL93 Operating: -1.00 RF

Bridge Scour and Storm Information

Pile Driving Record: No pile driving records
 Foundation Type: Foundation details
 Mode of Flow: Riverine
 Rating Scour Eval: Not Applicable
 Highest Scour Eval: Not Applicable
 Scour Evaluation Method: Unknown – Eval Not Comp

Scour Recommended I: No recommendation
 Scour Recommended II: No recommendation
 Scour Recommended III: No recommendation
 Scour Elevation: 99 ft
 Action Elevation: 99 ft
 Storm Frequency: 100

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM**

**Inspection/CIDR/Bridge Profile Report
CIDR**

REPORT ID: INSP005

Structure ID: 124142

DATE PRINTED: 3/18/2020

Elements

Inspection Date: 01/30/2020 TZAV

MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	8290 / 3	Channel	1	100	0	.	0	.	0	.	1 (EA)

MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	8478 / 3	MSE Walls	328	100	0	.	0	.	0	.	328 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	220 / 3	Re Conc Pile Cap/Ftg	228	100	0	.	0	.	0	.	228 ft

SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	8396 / 3	Other Abutment Slope Protection	1920	100	0	.	0	.	0	.	1920 (SF)

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	142 / 3	Other Arch	114	100	0	.	0	.	0	.	114 ft

SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
Structure Unit 1	333 / 3	Other Bridge Railing	64	100	0	.	0	.	0	.	64 ft

Total Number of Elements*: 6

*excluding defects/protective systems

Inspection Information**Inspection Date:** 01/30/2020**Type:** Regular NBI**Inspector:** KNMEIWR - William Ryan**Inspection Notes:** Sufficiency Rating Calculation Accepted by knmeiwr at 3/3/2020 3:04:39 PM**LOAD CAPACITY EVALUATION:**

The load rating dated 01/18/2019 applies to the current condition of this bridge.

NOTE: NBI (Item 47) horizontal clearance is 106ft. BrM does not accept input greater than 99.9ft. at the time of this report.

This is an initial inspection.

NON-STRUCTURAL ITEMS:**LIGHTING:**

The exterior face of the decorative lighting pillars at all four corners have protruding bolts and the northeast pillar is missing a light fixture and has exposed wires. Refer to Photos 3 and 4. REPAIR

SIDEWALKS:

The concrete sidewalk curbs for the hand rail have intermittent transverse cracks up to 1/32in.

The sidewalks have areas of water ponding.

**FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM****Inspection/CIDR/Bridge Profile Report
CIDR**

REPORT ID: INSP005

Structure ID: 124142

DATE PRINTED: 3/18/2020

Structure Notes

BRIDGE OWNER: LEE COUNTY PORT AUTHORITY

Structure inventoried from south to north.


TRAFFIC RESTRICTIONS: According to the load rating analysis dated 1/18/19, posting is not required. This structure is not posted.

Fill depth above crown= 2ft.


Schedule Notes

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM
Inspection/CIDR/Bridge Profile Report
Bridge Profile

Left Profile by Inspection



Right Profile by Inspection



FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR/Bridge Profile Report

Bridge Profile

DATE PRINTED: 3/18/2020 3:02:41 PM

Profile Data - Numerical Summary

Inspection Date and Key:	TZAV	Bent #	Left Height	Right Height	(All Heights are in Feet)
1/30/2020		1	13.30	13.50	
		1.5	14.20	15.50	
		2	13.30	13.80	

Air Temp:

Profile Notes:

Measurements referenced to top of sidewalk coping.
Waterline taken at centerline of channel: Left and Right = 11.3ft.

SECTION II
INVENTORY

II. INVENTORY

BRIDGE NUMBER: 124142
BRIDGE NAME: SKYPLEX BLVD BRIDGE

Inventory Topics

- A. Photo Inventory
- B. Location Map
- ** C. Condensed Inspection Data Report (SI&A)
- D. Load Capacity Information
- E. Bridge History
- F. Field Preparation
 - 1. Tools and Equipment
 - 2. Services
 - 3. Scheduling
 - 4. Site Conditions
- G. Bridge Description and Drawings
- * H. Identification of Fracture Critical Components
- I. Channel and Scour Information
 - 1. Channel Profile
 - * 2. Scour Screening and In-Depth Scour Evaluation

*Not included in this report.

**Included with Inspection Report

TOPIC A
PHOTO INVENTORY

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



BRIDGE NUMBER

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



SIDEWALK HANDRAIL

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



SOUTH APPROACH LOOKING NORTH

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



SOUTH APPROACH LOOKING SOUTH

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



NORTH APPROACH LOOKING SOUTH

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



NORTH APPROACH LOOKING NORTH

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



WEST ELEVATION

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



EAST ELEVATION

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



SUBSTRUCTURE

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



WEST CHANNEL

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



EAST CHANNEL

TOPIC B
BRIDGE LOCATION MAP

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020

LOCATION MAP



SKYPLEX BLVD BRIDGE

300 FT S/O CR-876

NOTE: DETOUR LENGTH = 1.1 MI

B1

TOPIC D

LOAD CAPACITY INFORMATION

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020

Bridge No. Skyplex Boulevard Bridge Analysis Method: LRFR-LRFD	FDOT Bridge Load Rating Summary Form (Page 1 of 1)
Location Skyplex Boulevard Bridge, Ft. Myers, FL - Lee County Port Authority	
Description Single Span FRP Composite Arch Bridge (32' Span)	

Rating Type	Rating Type	Gross Axle Weight (tons)	Moment/Shear/Service		Dead Load Factor	Live Load Factor	Live Load Distrib. Factor (axles)	Rating Factor	Span No., Girder No., Interior/Exterior, %Span-L	RF-Weight (tons)
Level	Vehicle	Weight	Member Type	Limit	DC	LL	LLDF	RF	Governing Location	RATING
Inventory	HL93	36	Reinf. Concrete	Strength, Moment	1.25/0.90	1.75		1.010	Interior Arch, Node 24, D.38L	36.4
Operating	HL93	36	Reinf. Concrete	Strength, Moment	1.25/0.90	1.35		1.310	Interior Arch, Node 24, D.38L	47.2
Permit	FL120	60	Reinf. Concrete	Strength, Moment	1.25/0.90	1.35		1.010	Interior Arch, Node 26, D.42L	60.6
Permit Max Span	FL120	60	Member Type	Limit Test	NA	NA		N/A		-1
Legal	SU2	17	Member Type	Limit Test	NA	NA				-1
	SU3	33	Member Type	Limit Test	NA	NA				-1
	SU4	35	Member Type	Limit Test	NA	NA				-1
	C3	28	Member Type	Limit Test	NA	NA				-1
	C4	36.7	Member Type	Limit Test	NA	NA				-1
	C5	40	Member Type	Limit Test	NA	NA				-1
	ST5	40	Member Type	Limit Test	NA	NA				-1

Original Design Load	HL93	Performed by:	Tim Kenerson	Date:	01/15/19
Rating Type, Analysis	LRFR-LRFD	Checked by:	Ken Sweeney	Date:	01/15/19
Distribution Method	Refined analysis	Sealed By:	Zeyn Uzman	Date:	01/17/19
Impact Factor	18.0% (axle loading)	FL P.E. No.:	58874		
FL120 Gov. Span Length	32.0 (feet)	Cert. Auth. No.:	State Agency		
Recommended Posting	At/Above legal loads. Posting Not Required.	Phone & email:	610-320-2100, zeynu@aol.com		
Recommended SU Posting*	99 (tons)	Company:	Uzman Engineering		
Recommended C Posting	99 (tons)	Address:	305 Charleston Green, Malvern, PA 19355		
Recommended ST5 Posting	99 (tons)				
Floor Beam Present?	No				
Segmental Bridge?	No				
Project No. & Reason	NA		New Bridge		
Plans Status	Built				
Software Name, Version	AIT FEA - 2.1				
COMMENTS BY THE ENGINEER					
Contents: summary, narrative, plans, calcs, check.					

D1

TOPIC E
BRIDGE HISTORY

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020

BRIDGE HISTORY

The structure was built in 2020 in Lee County.

The structure was designed by Advanced Infrastructure Technologies. The contractor was Thomas Marine Construction, Inc.

TOPIC F
FIELD PREPARATION

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
BRIDGE INSPECTION REPORT

TOPIC "F"
FIELD PREPARATION

Structure No.: 124142
Inspection Date: 1/30/2020

1. **Tools and Equipment:**

- | | |
|---|--|
| <input checked="" type="checkbox"/> Normal Inspection Tools | <input type="checkbox"/> Lift Barge |
| <input type="checkbox"/> Drone | <input type="checkbox"/> UB Access/ Bucket Truck |
| <input checked="" type="checkbox"/> Jon Boat / Kayak | <input type="checkbox"/> Other: _ |

2. **Services:**

N/A

3. **Scheduling:**

- Daytime Nighttime

4. **Site Conditions:**

- | | | | |
|--|--|--------------------------------|-----------------------------------|
| Provided / Estimated ADT: | 2350 | | |
| Provided / Estimated % of Truck Traffic: | 3% | | |
| Mode of Flow: | <input checked="" type="checkbox"/> Riverine | <input type="checkbox"/> Tidal | <input type="checkbox"/> Brackish |
| Embankment Conditions: | <input checked="" type="checkbox"/> Good | <input type="checkbox"/> Poor | |
| Vegetation Conditions: | <input checked="" type="checkbox"/> Good | <input type="checkbox"/> Poor | |
| Waterway: | <input checked="" type="checkbox"/> Good | <input type="checkbox"/> Poor | |

5. **Traffic Control Requirements:**

- MOT Other: _

6. **Underwater Inspection Requirements:**

- SCUBA Surface Supplied Air N/A

Underwater Elements Inspected: N/A

7. **Special Access Requirements:**

Refer to Structure Notes in the report for information for Special Access, if any.

8. **Manhours:**

- | | |
|--------------------------|--------------------------|
| Travel to and from site: | 2 hours x 2 people = 4 |
| Inspection hours: | 1.5 hours x 2 people = 3 |

9. **Plans Available:**


- Yes No

TOPIC G

BRIDGE DESCRIPTION AND DRAWINGS


FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020



FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT


Bridge No.: 124142
Inspection Date: 01/30/2020



FOUNDATION LAYOUT

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020




ADVANCED INFRASTRUCTURE TECHNOLOGERS
20 Gulfport Drive, Ocala, Florida 34472
Tel: 352.233.6200 | Fax: 352.233.6601 | www.aitech.com

DESIGNED BY TAK	PROJECT NAME Skyline Boulevard Roadway Improvements	DATE 8-27-2018
PROJECT FILE TAK	LOCATION Fort Meade, Florida	BY P. G. B. 1/16
DRAWN BY WH	DRAWING STATUS Construction Drawings	DRAWING NO. S. 03 - 2
CHK. MAN. RLS	DRAWING CONCRETE	SCALE 1"=1'-0"

TYPICAL SECTION

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020




TYPICAL DETAILS

G4


FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020




FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020



FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020



MSE WALLS DETAILS

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020

PERMANENT MSE RETAINING WALL SYSTEM DATA TABLES

GEOTECHNICAL INFORMATION						Table Date: 1-01-11
Depth Below Existing Ground Line (ft.)	Reinforced Soil & Random Backfill	Loose Fine Sand	Firm Fine Sand	Loose Clayey Fine Sand	Firm Clayey Fine Sand	
	Wall No. 1	---				
Wall No. 2	---					
Effective Unit Weight (pcf)	105					
Cohesion (psf)	0					
Internal Friction Angle	28°					

NOTE:
If the unit weight and/or internal friction angle of the fill proposed by the Contractor differs from that shown above, the Project Engineer will contact both the District Geotechnical Engineer and the Wall Designer for a possible redesign.

RETAINING WALL VARIABLES					Table Date: 7-01-12
Wall No.	Long Term Settlement (in.)	Short Term Settlement (in.)	Differential Settlement		Design High Water Elevation (ft.)
			Longitudinal (%)	Transverse (in.)	
1	1.0	0.5	N/A	N/A	
2	1.0	0.5	N/A	N/A	

NOTE:
Design walls for the settlements noted in the table.
Long term settlement is measured from the end of wall fill placement.
Transverse differential settlement is measured from the face of wall to the end of the soil reinforcement.

SOIL REINFORCEMENT LENGTHS FOR EXTERNAL STABILITY							Table Date: 1-01-11
Wall No.	Wall Height (ft.)	Reinforcement Length (ft.)					
		5	7	9	11	13	
1	Reinforcement Length (ft.)	8	10	12	13	16	
	Factored Bearing Resistance (psf)	3673	4209	4741	5789	6328	
	Wall Height (ft.)	5	7	9	11	13	
2	Reinforcement Length (ft.)	8	10	12	13	16	
	Factored Bearing Resistance (psf)	3673	4209	4741	5789	6328	
	Wall Height (ft.)	5	7	9	11	13	

NOTES:
1. The reinforcement strap lengths shown above are the minimum lengths required for external stability. The reinforcement lengths used in the construction of the retaining walls will be the longer of that required for external or internal stability (determined by proprietary wall companies).
2. The Factored Bearing Resistances shown above are the critical (lowest) values from all the load cases analyzed using LRFD methodology.

MSE RETAINING WALL GENERAL NOTES:


1. Concrete facing panel surfaces treatment will be Horizontal Stacked Stone / Slate and shall receive Class V Finish per FDOT Standard Specification 400-15.2.6 with the following colors (submit each for approval):
A. Wall Panels or Block: Text-Cote color Cream to match I-75 Direct Connect Walls
B. Wall Coping and Arch Coping: Federal Standard Color #30227 (or match)
C. Railing: Federal Standard Color #30227 (or match)
2. The Reinforced Soil Backfill shall be compacted granular material to an elevation 2-ft above HWH, and A-3 above that.
3. Applicable FDOT Wall Types for each wall location are listed below. See the Approved Products List for approved Wall Systems and Design Standards Index No. 6020 for allowable Wall Type substitutions.
Wall No. 1 - FDOT Wall Type 2E
Wall No. 2 - FDOT Wall Type 2E
4. Concrete for Coping and/or Junction Slab shall be Class IV (fc = 5,500 psi) with silica fume, metakaolin or ultrafine fly ash.
5. See Design Standards Index No. 6020 for General Notes and Details.
6. Submit panel treatment for approval.

ESTIMATED QUANTITIES			
Wall No.	Item	Unit	Quantity
1	Retaining Wall System, Permanent, Excluding Barrier	SF	1524
	Pedestrian/Bicycle Railing with Coping	LF	230
2	Retaining Wall System, Permanent, Excluding Barrier	SF	1524
	Pedestrian/Bicycle Railing with Coping	LF	230
1 - 2	Clean and Coat Concrete Finish, Class V	SF	3048

VINCENT ZAKRZASKAS P.E. P.L.C. LICENSE NUMBER 95224 PROGRESS ENGINEERING, INC. 2701 BUCKLE UP BOULEVARD SUITE 200 FORT WORTH, TX 76101 CERTIFICATE OF AUTHORIZATION 37889				LEE COUNTY PORT AUTHORITY		MSE RETAINING WALLS GENERAL NOTES & DATA TABLES SKYPLEX BOULEVARD ARCH BRIDGE	

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020




TIE BACK INCLUSION
PAGE 1 OF 2

G9

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM BRIDGE INSPECTION REPORT

Bridge No.: 124142
Inspection Date: 01/30/2020



TOPIC I

CHANNEL AND SCOUR INFORMATION

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



WEST CHANNEL

FLORIDA DEPARTMENT OF TRANSPORTATION
BRIDGE MANAGEMENT SYSTEM
STRUCTURE LEVEL INVENTORY REPORT

BRIDGE ID : 124142

Structure Inventory Photo Due Date : 01/30/2030



EAST CHANNEL


FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR/Bridge Profile Report


Bridge Profile

DATE PRINTED: 3/18/2020 3:02:41 PM

Left Profile by Inspection



Right Profile by Inspection



FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

Inspection/CIDR/Bridge Profile Report

Bridge Profile

Profile Data - Numerical Summary

Inspection Date and Key: 1/30/2020		TZAV		Bent #	Left Height	Right Height	(All Heights are in Feet)
				1	13.30	13.50	
				1.5	14.20	15.50	
				2	13.30	13.80	

Air Temp:

Profile Notes:

Measurements referenced to top of sidewalk coping.
Waterline taken at centerline of channel: Left and Right = 11.3ft.

SECTION III
COMMUNICATIONS

MEMORANDUM

Districts 1 & 7 Structures Maintenance Office
2916 Leslie Road, Tampa, FL 33619
(813) 975-7570 • Fax: (813) 975-7590

DATE: December 9, 2019
TO: Vince Zaliauskas, P.E.; HighSpans Engineering, Inc. 2121 McGregor Blvd. #200, Fort Myers, FL 33901
FROM: Tara Rodrigues, P.E., Engineering Section Manager
COPIES: Tara Rodrigues, P.E., Engineering Section Manager, Nico Antona, DBi; Vicki Griswold Hitch, DBi; Bridge Number Log
SUBJECT: **Bridge Number Assignment**

Your request for a Bridge Number Assignment has been granted as follows:

FINANCIAL PROJECT ID: N/A OWNER: COUNTY (Ex: State, County, City Name, Other [specify])
EOR name; Design firm, address: Vince Zaliauskas, P.E.; HighSpans Engineering, Inc. 2121 McGregor Blvd. #200, Fort Myers, FL 33901

COUNTY: Lee SECTION/SUBSECTION: 12000000 BEGIN M.P.: N/A(APPOX.)
(Refer to SLD's)

COUNTY ROAD NO.: N/A U.S./SR ROAD NO.: N/A
(Example: I-75/SR 93)

YEAR BUILT - PROPOSED: 2020 OR ACTUAL: _____ (if already built)
(Year Built (Proposed or Actual) pertains to the New Bridge Structure)

Bridge Character Description (please check):

COMPOSITE: LEFT: _____ RIGHT: _____ RAMP: _____
(Composite means two way traffic. "Left" or "Right" means - Facing Station Ahead: South to North/West to East)

LENGTH: 32 ft WIDTH: 114 ft
(The Length and Width Dimensions are for the New Bridge Structure. Bridge Culvert Length is parallel with Roadway)

BRIDGE NAME: Skyplex Blvd. Bridge
LOCATION: 309ft south of CR 876 Daniels Parkway [26°32'56.41"N / 81°45'31.10"W]
(Example: 1.5 miles North of SR 64 [optional: In addition to description use map software to provide Lat./Long.]

Bridge Over (please check): RAILROAD: _____ WATER: ROADWAY: _____

STRUCTURE TYPE: 2 (see options below)
(Based on Vertical under clearance)

- 1. OVERPASS
- 2. LOW (<20.0ft)
- 3. MEDIUM LEVEL (≥20.0ft – 45.0ft)
- 4. HIGH LEVEL (>45.0ft)
- 5. MOVEABLE SPAN
- 6. RAILROAD
- 7. OTHER (explain) _____
(i.e: Bridge Culvert, Segmental Cable Stay, Precast Box Culvert)

FA _____ NFA

Note: 08, 09, & 19 = NFA

FUNCTIONAL CLASSIFICATION OF INVENTORY

ROUTE CODE: 19 (see options below)

- Code Description
- Rural
 - 01 Principal Arterial – Interstate
 - 02 Principal Arterial – Other
 - 06 Minor Arterial
 - 07 Major Collector
 - 08 Minor Collector
 - 09 Local
 - Urban
 - 11 Principal Arterial – Interstate
 - 12 Principal Arterial – Other Freeways or Expressways
 - 14 Other Principal Arterial
 - 16 Minor Arterial
 - 17 Collector
 - 19 Local

EXISTING BRIDGE NUMBER TO BE REPLACED: N/A
NEW BRIDGE NUMBER ASSIGNED: 124142

DATE: 12/19/19

TO: James J. Jacobsen, P.E., District 1 and 7 Structures Maintenance Engineer;

FROM: Vince Zaliauskas, P.E. Principal Engineer HighSpans Engineering, Inc.

COPIES: Tara Rodrigues, P.E., Engineering Section Manager, Doug Schallmoser, E.I., Structures Project Manager

SUBJECT: REQUEST FOR INITIAL BRIDGE INSPECTION

Please complete this form for each bridge or culvert with a total length of 20 feet or greater on your project. The Initial Inspection date should be requested after the structure is substantially complete, preferably before the contractor leaves the job site. However, the Initial Inspection must be done, before the bridge or culvert is opened to traffic.

The Engineer of Record must confirm that the Design Load Rating is still applicable or produce a revised As-Built Load Rating in accordance with CPAM 10.11.4 if any changes made during construction affect the capacity of the structure. If the Design Load Rating is still applicable, a signed and sealed As-Built Letter and a new load rating summary sheet specifying the load rating origination field as "As-Built" must be submitted. However, if an As-Built Load Rating is produced, such must be submitted as an "As-Built Load Rating" and the load rating origination field on the load rating summary sheet shall also be specified as "As-Built" with the accompanying new backup calculations.

BRIDGE INFORMATION:

BRIDGE NUMBER: 124142 BRIDGE NAME: Skyplex Blvd. Bridge

BRIDGE LOCATION: 309ft south of CR 876 Daniels Parkway [26°32'56.41"N / 81°45'31.10"W]

COUNTY: Lee

SECTION/SUBSECTION: 12000000 (refer to SLDs)

ROAD NUMBER: N/A M.P. AND/OR STATION: N/A

BRIDGE OVER: RAILROAD: WATER: ROADWAY:

PROJECT INFORMATION:

FPN or SPN: N/A SCHEDULED COMPLETION DATE: 2020

SCHEDULED FINAL CONSTRUCTION INSPECTION DATE: 1/07/2020

	YES	NO
HAS ALL CONCRETE AND STEEL BEEN PLACED?	<input checked="" type="radio"/>	<input type="radio"/>
ARE ALL SURFACES AVAILABLE FOR INSPECTION? (FREE OF DEBRIS, FORMS, MATERIALS)	<input checked="" type="radio"/>	<input type="radio"/>
EQUIPMENT/MATERIAL HAS BEEN REMOVED OVER AND UNDER STRUCTURE TO FACILITATE INSPECTION?	<input checked="" type="radio"/>	<input type="radio"/>
ARE ALL TRAFFIC BARRIERS / RAILINGS PLACED?	<input checked="" type="radio"/>	<input type="radio"/>
ARE BOTH APPROACH SLABS PLACED?	<input checked="" type="radio"/>	<input type="radio"/>

Highway Bridge Inspection Report

BR# 0077

ROYAL RIVER

OLD DANVILLE RD

Over

ROYAL RIVER

Town:

Auburn



Inspection Date: 11/13/2020

Inspected By: Kleinfelder, Kleinfelder

Inspection Type(s): Routine

Inspector: Kleinfelder Kleinfelder


Structure Number: 0077

Inspection Date: 11/13/2020

Facility Carried: OLD DANVILLE RD

Highway Bridge Inspection Report

Location Map



Latitude: 44.01493

Longitude: -70.27187

National Bridge Inventory

Status: 0 - ND

Bridge Name: ROYAL RIVER

Sufficiency Rating: 97.0

Inspections

(90) INSPECTION DATE	& (91) DESIGNATED INSPECTION FREQUENCY	24	11/13/2020
(92) CRITICAL FEATURE INSPECTION	& (93) CFI DATE		
(92A) FRACTURE CRITICAL DETAIL		N	
(92B) UNDERWATER INSPECTION		N	
(92C) OTHER SPECIAL INSPECTION		N	

Identification

(1) STATE CODE	231 - Maine
(8) STRUCTURE NUMBER	0077
(5) INVENTORY ROUTE	
(5A) RECORD TYPE	1: Route carried "on" the structure
(5B) ROUTE SIGNING PREFIX	5 - CITY STREET
(5C) DESIGNATED LEVEL OF SERVICE	0 - None
(5) INVENTORY ROUTE	0
(5) INVENTORY ROUTE	0 - NOT APPLICABLE
(2) HIGHWAY AGENCY DISTRICT	01 - Southern
(3) COUNTY CODE	001 Androscoggin
(4) PLACE CODE	02060
(6) FEATURES INTERSECTED	ROYAL RIVER
(7) FACILITY CARRIED	OLD DANVILLE RD
(9) LOCATION	1.8 MI N RT 5 202 /100/4
(11) MILEPOINT	0
(12) BASE HIGHWAY NETWORK	Inventory Route is not on the Base Network
(13) LRS INVENTORY ROUTE, SUBROUTE	
(13A) LRS INVENTORY ROUTE	0000110290
(13B) SUBROUTE NUMBER	00
(16) LATITUDE	44.01493
(17) LONGITUDE	-70.27187
(98A) BORDER BRIDGE CODE	
(98B) PERCENT RESPONSIBILITY	0
(99) BORDER BRIDGE STRUCT NO.	n/a

Structure Type and Material

(43) STRUCTURE TYPE, MAIN	
(43A) KIND OF MATERIAL/DESIGN	0 - Other
(43B) TYPE OF DESIGN/CONSTR	19 - Culvert (includes frame culverts)
(44) STRUCTURE TYPE, APPROACH SPANS	
(44A) KIND OF MATERIAL/DESIGN	0 - Other
(44B) TYPE OF DESIGN/CONSTRUCTION	00 - Other
(45) NUMBER OF SPANS IN MAIN UNIT	1
(46) NUMBER OF APPROACH SPANS	0
(107) DECK STRUCTURE TYPE	N - Not Applicable
(108) WEARING SURFACE/PROTECTIVE SYSTEMS	
(108A) WEARING SURFACE	N - NA
(108B) DECK MEMBRANE	N - NA
(108C) DECK PROTECTION	N - NA

Age of Service

(27) YEAR BUILT	2010
(106) YEAR RECONSTRUCTED	0
(42) TYPE OF SERVICE	
(42A) TYPE OF SERVICE ON BRIDGE	1 - Highway
(42B) TYPE OF SERVICE UNDER BRIDGE	5 - Waterway
(28) LANES	
(28A) LANES ON THE STRUCTURE	02
(28B) LANES UNDER THE STRUCTURE	00
(29) AVERAGE DAILY TRAFFIC	210
(30) YEAR OF AVERAGE DAILY TRAFFIC	2016
(109) AVERAGE DAILY TRUCK TRAFFIC	5
(19) BYPASS DETOUR LENGTH	1

Geometric Data

(48) LENGTH OF MAXIMUM SPAN (ft.)	38.0
(49) STRUCTURE LENGTH (ft.)	38.0
(50) CURB/SIDEWALK WIDTHS	
(50A) LEFT CURB SIDEWALK (ft.)	0
(50B) RIGHT CURB SIDEWALK (ft.)	0
(51) BRDG RDWY WIDTH CURB-TO-CURB (ft.)	0
(52) DECK WIDTH, OUT-TO-OUT (ft.)	0
(32) APPROACH ROADWAY WIDTH (ft.)	26.0
(33) BRIDGE MEDIAN	0 - No median
(34) SKEW (deg.)	15
(35) STRUCTURE FLARED	0 - No flare
(10) INV RTE, MIN VERT CLEARANCE (ft.)	328.05
(47) TOTAL HORIZONTAL CLEARANCE (ft.)	28.0
(53) VERTICAL CLEARANCE OVER BRIDGE ROADWAY (ft.)	327.76
(54) MIN VERTICAL UNDERCLEARANCE	
(54A) REFERENCE FEATURE	N - Feature not a highway or railroad
(54B) MIN VERTICAL UNDERCLEASENCE (ft.)	0
(55) MIN LATERAL UNDER CLEARANCE RIGHT	
(55A) REFERENCE FEATURE	N - Feature not a highway or railroad
(55B) MIN LATERAL UNDER CLEARANCE RIGHT (ft.)	327.76
(56) MIN LATERAL UNDER CLEARANCE (ft.)	99.9

Classification

(112) NBIS BRIDGE LENGTH	Yes
(104) HIGHWAY SYSTEM OF THE INVENTORY ROUTE	0 - Structure/Route is NOT on NHS
(26) FUNCTIONAL CLASSIFICATION OF INVENTORY ROUTE	19 - Urban - Local
(100) STRAHNET HIGHWAY DESIGNATION	Not a STRAHNET route
(101) PARALLEL STRUCTURE DESIGNATION	N - No parallel structure
(102) DIRECTION OF TRAFFIC	2-way traffic
(103) TEMP STRUCTURE	
(105) FEDERAL LANDS HIGHWAYS	Not Applicable
(110) DESIGNATED NATIONAL NETWORK	Inventory route not on network
(20) TOLL	3 - On Free Road
(21) MAINTENANCE RESPONSIBILITY	01 - State Highway Agency
(22) OWNER	01 - State Highway Agency
(37) HISTORICAL SIGNIFICANCE	4 - Not determinable

Condition

(58) DECK	N - Not Applicable
(59) SUPERSTRUCTURE	N - Not Applicable
(60) SUBSTRUCTURE	N - Not Applicable
(61) CHANNEL & CHANNEL PROTECTION	9 - No noticeable deficiencies
(62) CULVERT	8 - No noticeable or noteworthy deficiencies

Load Rating and Posting

(31) DESIGN LOAD	9 - HS 25 or greater
(63) METHOD USED TO DETERMINE OPERATING RATING	8 - Load and Resistance Factor Rating (LRFR) rating report by rating factor (RF) method using HL-93 loadings.
(64) OPERATING RATING	1.61
(65) METHOD USED TO DETERMINE INVENTORY RATING	8 - Load and Resistance Factor Rating (LRFR) rating report by rating factor (RF) method using HL-93 loadings.
(66) INVENTORY RATING	1.24
(70) BRIDGE POSTING	5 - Equal to or above legal loads
(41) STRUCTURE OPEN/POSTED/CLOSED	A - Open

Appraisal

(67) STRUCTURAL EVALUATION	8
(68) DECK GEOMETRY	N
(69) UNDERCLEARANCES, VERTICAL & HORIZONTAL	N
(71) WATERWAY ADEQUACY	8 - Bridge Above Approaches
(72) APPROACH ROADWAY ALIGNMENT	6 - Equal to present minimum criteria
(36) TRAFFIC SAFETY FEATURE	
36A) BRIDGE RAILINGS:	0 - Does not meet acceptable standards/safety feature is required
36B) TRANSITIONS:	0 - Does not meet acceptable standards/safety feature is required
36C) APPROACH GUARDRAIL	0 - Does not meet acceptable standards/safety feature is required

36D) APPROACH GUARDRAIL ENDS
(113) SCOUR CRITICAL BRIDGES

0 - Does not meet acceptable standards/safety feature is required
8 - Stable for scour conditions

Proposed Improvements

(75) TYPE OF WORK	
(75A) TYPE OF WORK PROPOSED	
(75B) WORK DONE BY	
(76) LENGTH OF STRUCTURE IMPROVEMENT (ft.)	
(94) BRIDGE IMPROVEMENT COST (\$K)	
(95) ROADWAY IMPROVEMENT COST (\$K)	
(96) TOTAL PROJECT COST	
(97) YEAR OF IMPROVEMENT COST ESTIMATE	
(114) FUTURE ADT	336
(115) YEAR OF FUTURE ADT	2036

Navigation Data

(38) NAVIGATION CONTROL	0 - No navigation control on waterway (bridge permit not required)
(111) PIER OR ABUTMENT PROTECTION	
(39) NAV VERT CLEARANCE	0
(116) MIN NAVIGATION VERT CLEARANCE, VERT LIFT BRIDGE	0
(40) NAV HORIZONTAL CLEARANCE	0

Inspection Notes

Structure Number: 0077

Town: Auburn

Structure Name: ROYAL RIVER

Structure Notes

44' Single span bridge in a backpack. Reinforced fiberglass concrete filled tube arches. Composite formed concrete slab over. Pile supported concrete footings. Buried structure.

Wearing Surface

Deck NBI Item 58: N

Superstructure NBI Item 59: N

Substructure NBI Item 60: N

Culvert NBI Item 62: 8

Culvert in very good condition with scattered minor cracking and efflo stains in footings , Arch fascia and cast in place portion of walls.

Channel NBI Item 61: 9

No problems noted. Well centered channel

Other

Special Inspection

Monitoring

Pontis Notes

Inspector: Kleinfelder Kleinfelder

Structure Number: 0077

Inspection Date: 11/13/2020

Facility Carried: OLD DANVILLE RD

Highway Bridge Inspection Report

Element Inspection

	Environment	Total Quantity	Units	Condition State 1	Condition State 2	Condition State 3	Condition State 4
243 - Other Culvert	2 - Low	70	ft.	70	0	0	0
824 - Prefabricated Concrete Wall	2 - Low	140	ft.	140	0	0	0

Over Limit Report

Bridge #: 0077
 Bridge Name: ROYAL RIVER
 Owner: 01 - State Highway Agency
 Co-Owner: N Not applicable
 Region: 01 - Southern

Town1: Auburn
 Town2:
 Maintainer: 01 - State Highway Agency
 Co-Maintainer: N Not applicable

Vertical Clearance - Under		<i>Left, Center, and Right is based on the direction of travel</i>					
<u>Roadway - Heading North or East</u>		Actual Heights in Feet-Inches				Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>	<u>Posted</u>	<u>Deficient Sign</u>	
Main:	<input type="text" value="ROYAL RIVER"/>	-	-	-	<input type="checkbox"/> Main	-	
Other:	<input type="text"/>	-	-	-	<input type="checkbox"/> Other	-	
	Ramps:	-	-	-	<input type="checkbox"/> Ramp	-	
<u>Roadway - Heading South or West</u>		Actual Heights in Feet-Inches				Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>	<u>Posted</u>	<u>Deficient Sign</u>	
Main:	<input type="text" value="ROYAL RIVER"/>	-	-	-	<input type="checkbox"/> Main	-	
Other:	<input type="text"/>	-	-	-	<input type="checkbox"/> Other	-	
	Ramps:	-	-	-	<input type="checkbox"/> Ramp	-	

Vertical Clearance - Portal		Roadway: <input type="text" value="OLD DANVILLE RD"/>					
<u>Heading North or East</u>		Actual Heights in Feet-Inches				Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>	<u>Posted</u>	<u>Deficient Sign</u>	
		-	-	-	<input type="checkbox"/> Portal	-	
<u>Heading South or West</u>		Actual Heights in Feet-Inches				Date Measured:	
		<u>Left</u>	<u>Center</u>	<u>Right</u>	<u>Posted</u>	<u>Deficient Sign</u>	
		-	-	-	<input type="checkbox"/> Portal	-	

Permitting		<u>Pointer</u>	<input type="checkbox"/> Red Flag Comments
Heading North Height:	-		
Heading South Height:	-		
Left Ramp Height:	-		
Right Ramp Height:	-		
Portal North Height:	-		
Portal South Height:	-		
Other Road Height:	-		
Bridge Width:	0 ft		
Roadway Width:	26.0 ft		
Underclearance heights are signed if less than 14 ft 6 in Check with Maine Turnpike Authority for load heights over 13 ft 6 in Always check 511			

Load Restrictions		tons	Date posted:
Posted			
Posted One Truck at aTime			
Posted for 4 axle only			
Operating Load Rating	1.61		
Permit Load Ratings		axles	
		axles	
		axles	

Inspector: Kleinfelder Kleinfelder

Structure Number: 0077

Inspection Date: 11/13/2020

Facility Carried: OLD DANVILLE RD

Highway Bridge Inspection Report

Pictures



PHOTO 1

Description Approach looking north



PHOTO 2

Description Approach looking south

Inspector: Kleinfelder Kleinfelder

Structure Number: 0077

Inspection Date: 11/13/2020

Facility Carried: OLD DANVILLE RD

Highway Bridge Inspection Report

Pictures



PHOTO 3

Description Guardrail damage



PHOTO 4

Description Guardrail damage upstream rail

Highway Bridge Inspection Report

Pictures



PHOTO 5

Description Downstream Elevation View



PHOTO 6

Description Upstream Elevation View

Highway Bridge Inspection Report

Pictures



PHOTO 7

Description Channel typical, well centered and protected



PHOTO 8

Description Small cracks in arch fascia concrete

Highway Bridge Inspection Report

Pictures



PHOTO 9

Description Small cracks in concrete arch fascia



PHOTO 10

Description Small crack and leaking in arch fascia concrete

Highway Bridge Inspection Report

Pictures



PHOTO 11

Description Typical footing and rib interface



PHOTO 12

Description Footing and arch rib connection

MaineDOT NBIS Bridge Safety Inspection JSA

Inspector: Kleinfelder, Kleinfelder
er
Team Lead: Michael Falla

Structure Number: 0077
Structure Name: ROYAL RIVER
Town: Auburn

Additional Team Members/Visitors:

- | | |
|-------------------|-----|
| 1.) Tim Merrithew | 6.) |
| 2.) | 7.) |
| 3.) | 8.) |
| 4.) | 9.) |
| 5.) | |

Job being performed:

Routine bridge inspection.

Potential Hazard:

- Exposure to traffic

Potential Hazard:

- Steep slopes and uneven working areas
(rip rap, mud, loose fill, etc)

Potential Hazard:

- Chipped Concrete or Steel (hand tools only)

Potential Hazard:

- 6' Vertical drops

Potential Hazard:

- Water Hazards

- Water depth under 1 foot
- Water depth 1 to 4 feet
- Water depth over 4 feet
- Water flow calm/slow moving
- Water flow visible/not rapid
- Water flow rapid with some short falls
- Tidal Water

Potential Hazard:

Controls:

- Parked off road with strobe
- Less than 1 hour on bridge
- Wear standard reflective clothing and hard hat
- Spotter Traffic Control Crew

Controls:

- Wear appropriate, prudent footwear
- Rope or fall protection

Controls:

- Wear appropriate, prudent eye/hand protection

Controls:

- Stay away from areas

Controls:

- Evaluate Water Hazard conditions
- Use/Wear appropriate PPE
- Buddy System

Controls:

Insects, Poison Ivy, or other environmental hazards

Potential Hazard:

Lead paint and Avian excrement

Potential Hazard:

Heavy Manual Lifting

Potential Hazard:

DCS, Lung Expansion

Potential Hazard:

Entanglement U/W

Potential Hazard:

Boat Traffic

Potential Hazard:

Cold Water

Potential Hazard:

Live Boating

Other Potential Hazards:

Safety Equipment Required:

-

Apply insect repellent and/or sunscreen

Protect skin with appropriate, prudent clothing

Controls:

Wear gloves, do not scrape

Controls:

Ask for assistance in donning dive gear, lifting equipment

Controls:

Ascend slowly, use computers, Safety Stops (15' mark for 3 min.)

Controls:

Use knife, Comm gear

Controls:

Fly Dive Flag, use spotter, contact bridge on Chan. 13

Controls:

Use adequate dry suit underwear for water temperature

Controls:

Keep track of divers, avoid powering during drop-off/pick-up

Other Controls:

Emergency Action Plan:

Hard hat

- Vest
- Glasses
- Gloves
- PFD
- Rain Gear
- Bug Spray

Sunscreen

- First Aid
- O2
- AED
- Comm Gear
- Cell Phone
- Boat

Throw Ring

- Throw Rope
- Positioning Device

Call 911

- First Aid Kit
- Fall Rescue Plan
- Water Rescue Plan
- Dan 1-919-684-9111
- USCG 741-5465

Other Safety Equipment:

Other Emergency Action Plan:

I certify that the MaineDOT NBIS Bridge Safety Inspection JSA has been completed according to all proper procedures required by the Maine Department of Transportation.

Complete Michael Falla

Bridge Components

Bridge #: 0077
 Bridge Name: ROYAL RIVER
 Owner: 01 - State Highway Agency
 Co-Owner: N Not applicable
 Region: 01 - Southern

Town1: Auburn
 Town2:
 Maintainer: 01 - State Highway Agency
 Co-Maintainer: N Not applicable

Deck

<u>Joint Seal Type/MFG:</u>		<u>Joint Types:</u>		<u>Joint HDR Mat:</u>	<u>Other:</u>	<u>Rebar Type:</u>
<input type="checkbox"/> Emseal	<input type="checkbox"/> V Seal	<input type="checkbox"/> Finger	<input type="checkbox"/> Asphaltic Plug	<input type="checkbox"/> Concrete	<input type="checkbox"/> Curtain	
<input type="checkbox"/> Watson Bowman	<input type="checkbox"/> Hot Rubber	<input type="checkbox"/> Compression	<input type="checkbox"/> Modular	<input type="checkbox"/> Delcrete	<input type="checkbox"/> Troughs	
<input type="checkbox"/> Pour-in-Place	<input type="checkbox"/> DS Brown	<input type="checkbox"/> Gland	<input type="checkbox"/> Waybo Crete	<input type="checkbox"/> Elastomeric	<input type="checkbox"/> Armor	
		<input type="checkbox"/> Sliding	<input type="checkbox"/> Transflex	<input type="checkbox"/> LP Concrete		
		<input type="checkbox"/> Open		<input type="checkbox"/> Phoscrete		
				<input type="checkbox"/> Plycrete		

Superstructure

<u>Left Side Rail:</u>			<u>Right Side Rail:</u>		
Material	Steel	<input type="checkbox"/> Retrofit	Material	Steel	<input type="checkbox"/> Retrofit
Shape	Guardrail	<input type="checkbox"/> Safety Walk	Shape	Guardrail	<input type="checkbox"/> Safety Walk
Attached To	Ground	<input type="checkbox"/> Pales	Attached To	Ground	<input type="checkbox"/> Pales
Number of Bars	0	<input type="checkbox"/> Snow Fence	Number of Bars	0	<input type="checkbox"/> Snow Fence
Extra Height	N		Extra Height	N	

<u>Bearing Type Quantity:</u>		<u>Fatigue Prone Detail:</u>			
<input type="checkbox"/> Disk	<input type="checkbox"/> Elastomeric	<input type="checkbox"/> Narrow Cover Plate - Sq End Welded	<input type="checkbox"/> Narrow Cover Plate - Tapered End Welded		
<input type="checkbox"/> Pot	<input type="checkbox"/> Rocker	<input type="checkbox"/> Narrow Cover Plate - Sq End w/o Weld	<input type="checkbox"/> Narrow Cover Plate - Tapered End w/o Weld		
<input type="checkbox"/> Roller	<input type="checkbox"/> Sliding Plate	<input type="checkbox"/> Wide Cover Plate - Sq End Welded	<input type="checkbox"/> Longitudinal Stiffener - Welded with Radius		
<u>Other:</u>		<input type="checkbox"/> Wide Cover Plate - Sq End w/o Weld	<input type="checkbox"/> Longitudinal Stiffener - Welded w/o Radius		
<input type="checkbox"/> Pin Quantity		<input type="checkbox"/> Lateral Connection Plate - Welded	<input type="checkbox"/> Hoan Detail		
<input type="checkbox"/> Pin and Link Quantity					

Substructure

<input type="checkbox"/> Pier Collars	<u>Retaining Wall Type:</u>
<input type="checkbox"/> Abutment Collars	T-Wall
<input type="checkbox"/> Wood Piles	
<input type="checkbox"/> Steel Piles	
<input type="checkbox"/> Blocked Bridge	

Other

Confined Space
 Bridge Lighting
 Cat Walk
 Navigational Lighting
 Signs Attached

General Notes

Bridge Preservation

Bridge #: 0077
 Bridge Name: ROYAL RIVER
 Owner: 01 - State Highway Agency
 Co-Owner: N Not applicable
 Region: 01 - Southern

Town1: Auburn
 Town2:
 Maintainer: 01 - State Highway Agency
 Co-Maintainer: N Not applicable

<p>Deck</p> <p><u>NBI Deck Information:</u></p> <p>Deck Type N - Not Applicable</p> <p>Deck Protection N - NA</p> <p>Membrane Type N - NA</p> <p style="text-align: right;"><u>Wearing Surface:</u></p> <p style="text-align: right;">Type N - NA</p> <p style="text-align: right;">Last Date</p> <p style="text-align: right;">Lifespan (Yrs)</p> <p style="text-align: right;">Next Date Est. 0</p> <p style="text-align: right;">Mill & Fill Date</p> <hr/> <p>Superstructure</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 33%;"><u>Beam Ends Paint:</u></td> <td style="width: 33%;"><u>Bearings Paint:</u></td> <td style="width: 33%;"><u>Bearings Lubrication:</u></td> </tr> <tr> <td>Last Date</td> <td>Last Date</td> <td>Last Date</td> </tr> <tr> <td>Next Date Est.</td> <td>Next Date Est.</td> <td>Next Date Est.</td> </tr> </table> <table style="width: 100%; border: none; margin-top: 10px;"> <tr> <td style="width: 33%;"><u>Beam Ends Fluid Film:</u></td> <td style="width: 33%;"><u>Bearings Fluid Film:</u></td> <td style="width: 33%;"><u>Treatment:</u></td> </tr> <tr> <td>Last Date</td> <td>Last Date</td> <td><input type="checkbox"/> Core 10</td> </tr> <tr> <td>Next Date Est.</td> <td>Next Date Est.</td> <td><input type="checkbox"/> Galvanized</td> </tr> <tr> <td></td> <td></td> <td><input type="checkbox"/> Metalized</td> </tr> </table> <hr/> <p>Substructure</p>	<u>Beam Ends Paint:</u>	<u>Bearings Paint:</u>	<u>Bearings Lubrication:</u>	Last Date	Last Date	Last Date	Next Date Est.	Next Date Est.	Next Date Est.	<u>Beam Ends Fluid Film:</u>	<u>Bearings Fluid Film:</u>	<u>Treatment:</u>	Last Date	Last Date	<input type="checkbox"/> Core 10	Next Date Est.	Next Date Est.	<input type="checkbox"/> Galvanized			<input type="checkbox"/> Metalized	<p>Common Preservation</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"><u>Paint Information:</u></td> <td style="width: 50%;"><u>Anodes:</u></td> </tr> <tr> <td>Type</td> <td><input type="checkbox"/> Installed</td> </tr> <tr> <td>Last Date</td> <td><input type="checkbox"/> Detached</td> </tr> <tr> <td>Lifespan (Yrs)</td> <td><input type="checkbox"/> Replace</td> </tr> <tr> <td>Next Date Est. 0</td> <td></td> </tr> </table> <hr/> <table style="width: 100%; border: none;"> <tr> <td style="width: 50%;"><u>Concrete-Silane:</u></td> <td style="width: 50%;"><u>Washing:</u></td> </tr> <tr> <td>Last Date</td> <td><input type="checkbox"/> Required</td> </tr> <tr> <td>Next Date Est.</td> <td><input type="checkbox"/> UBIT</td> </tr> </table> <hr/> <p><u>Concrete-Linseed</u></p> <p>Last Date</p> <p>Next Date Est.</p> <p><input type="checkbox"/> Alkali-Silica reactivity</p>	<u>Paint Information:</u>	<u>Anodes:</u>	Type	<input type="checkbox"/> Installed	Last Date	<input type="checkbox"/> Detached	Lifespan (Yrs)	<input type="checkbox"/> Replace	Next Date Est. 0		<u>Concrete-Silane:</u>	<u>Washing:</u>	Last Date	<input type="checkbox"/> Required	Next Date Est.	<input type="checkbox"/> UBIT
<u>Beam Ends Paint:</u>	<u>Bearings Paint:</u>	<u>Bearings Lubrication:</u>																																				
Last Date	Last Date	Last Date																																				
Next Date Est.	Next Date Est.	Next Date Est.																																				
<u>Beam Ends Fluid Film:</u>	<u>Bearings Fluid Film:</u>	<u>Treatment:</u>																																				
Last Date	Last Date	<input type="checkbox"/> Core 10																																				
Next Date Est.	Next Date Est.	<input type="checkbox"/> Galvanized																																				
		<input type="checkbox"/> Metalized																																				
<u>Paint Information:</u>	<u>Anodes:</u>																																					
Type	<input type="checkbox"/> Installed																																					
Last Date	<input type="checkbox"/> Detached																																					
Lifespan (Yrs)	<input type="checkbox"/> Replace																																					
Next Date Est. 0																																						
<u>Concrete-Silane:</u>	<u>Washing:</u>																																					
Last Date	<input type="checkbox"/> Required																																					
Next Date Est.	<input type="checkbox"/> UBIT																																					
<p>General Notes</p> 																																						

[END OF DOCUMENT]